



ABBREVIATIONS

BO	Base Drop	IRF	Iron Railing Fence
BL	Base Level	IPF	Interwoven Fence
BN	Base Note	LP	Lead Pipe
B	Boilers	ML	Man Hole
BP	Brick Paviors	MR	Mortar
BWR	Brick Retaining Wall	P	Post
CB	Control Box	PM	Plastic Handrail
CBF	Class Boarded Fence	PMF	Parade Meter
CCB	Cable TV Control Box	PPF	Post & Rail Fence
CD	Channel Drain	RE	Resin Stone
CFP	Chestnut Paling Fence	RD	Rough Ground
CLF	Chain Link Fence	RL	Ridge Level
CPF	Concrete Panel Fence	RS	Road Sign
CPS	Concrete Paving Slabs	RSI	Road Sign
CWR	Concrete Retaining Wall	S	Spread
CTV	Cable Television	SC	Shop Cock
CU	Concrete Wall	SL	Soffit Level
D	Diameter	SPS	Stone Paving Slabs
DP	Down Pipe	SRW	Stone Retaining Wall
ECB	Electricity Control Box	SU	Stop Up
EL	Level	SW	Stone Wall
EP	Electricity Pole	TB	Telco Box
F	Flower Bed	TF	Tactile Paving Slabs
FB	Fire Hydrant	TL	Traffic Light
FL	Flat Roof Level	TP	Telephone Pole
FR	Flat Roof Level	TPF	Traffic Panel Fence
H	Height to Watert	UTL	Under To Lint
IV	Inspection Cover	VP	Vent Pipe
IC	Inspection Cover	WL	Water Level
IL	Invert Level	WR	Water Meter
		WV	Water Valve

NOTES:
ALL LEVELS RELATE TO SURVEY STATION No 101 IN VERGE

TREE SCHEDULE

No.	DIA	SPREAD	HEIGHT	TYPE
1	1.2	12	20	OAK
2	0.2	10	15	UNKNOW
3	0.25	10	15	STYCAMORE
4	0.25	10	15	DEAD - REMOVED
5	1.5	10	20	OAK
6	0.3	10	15	STYCAMORE
7	0.3	10	15	STYCAMORE
8	0.25	10	15	STYCAMORE
9	0.25	10	15	STYCAMORE
10	0.3	10	15	STYCAMORE
11	0.25	10	15	STYCAMORE
12	0.3	12	15	STYCAMORE
13	0.4	10	15	STYCAMORE
14	0.15	0	20	PIRE
15	0.8	0	18	ASH
16	0.45	18	20	OAK
17	0.7	15	18	OAK
18	1.2	18	20	OAK
19	0.4	14	20	STYCAMORE
20	0.2	5	10	SHED
21	0.3	10	18	STYCAMORE
22	0.45	3	15	DEAD
23	1.0	20	24	OAK
24	0.3	10	17	STYCAMORE
25	1.0	18	20	OAK
26	0.8	12	20	PIRE
27	0.15	10	25	STYCAMORE
28	0.7	18	25	STYCAMORE
29	0.35	12	18	STYCAMORE
30	0.2	10	18	STYCAMORE
31	1.1	20	20	OAK
32	0.25	10	20	STYCAMORE
33	0.2	10	15	STYCAMORE
34	0.8	10	18	STYCAMORE
35	0.15	0	0	ASH
36	0.6	10	24	OAK
37	0.25	10	18	STYCAMORE
38	0.4	20	15	BEECH
39	0.8	22	18	OAK
40	1.0	18	18	BEECH
41	0.75	18	18	SILVER BIRCH
42	1.0	17	20	LINE
43	0.8	0	0	LINE
44	0.7	10	24	LINE
45	0.8	10	17	BEECH
46	0.3	0	10	SPRUCE
47	0.8	18	22	OAK
48	0.15	0	0	CYPRESS
49	0.15	0	0	CYPRESS
50	0.15	0	0	CYPRESS
51	0.25	1	10	ROSE
52	0.25	1	10	BEECH
53	0.2	0	10	OAK
54	0.2	0	10	OAK
55	0.2	0	10	OAK
56	0.2	0	10	OAK
57	0.2	0	10	OAK
58	0.2	0	10	OAK
59	0.25	0	15	LINE
60	0.15	0	0	APPLE
61	0.3	14	20	STYCAMORE
62	0.3	10	15	CHERRY
63	0.25	10	15	CHERRY
64	0.2	12	10	CHERRY
65	0.4	10	18	CHERRY - REMOVED
66	0.3	14	10	STYCAMORE
67	0.3	14	10	STYCAMORE
68	0.8	12	20	ASH
69	0.25	12	17	STYCAMORE
70	0.25	12	10	STYCAMORE
71	1.0	20	20	OAK
72	0.45	10	20	STYCAMORE
73	0.3	0	7	HARTHORN

CONTROL SCHEDULE

STM	EASTING	NORTHING	LEVEL
100	186.547	478.508	51.301
101	206.008	508.000	50.000
102	236.205	492.588	48.430
103	225.000	478.378	48.161
104	237.054	445.332	50.810
105	232.905	431.017	51.200
106	206.875	436.816	51.000
107	186.500	451.245	50.992
108	182.318	488.082	51.000
200	184.284	422.088	52.212
301	162.157	482.582	51.007
201	275.050	585.587	48.878
302	295.005	488.128	50.878

WELWYN HARTFIELD
PLANNING
OFFICE COPY
23 OCT 2009
2009/2273

COPYRIGHT: The contents of this drawing may not be reproduced in part or in whole without the written consent of Building Design Consultants

PROJECT: Proposed extension & alterations
DRAWING NUMBER: 09044/4

DRAWING: Proposed site plan - A1 SHEET

CLIENT: Mr and Mrs P Vicary

SITE: Vine Cottage
The Ridgeway
Northaw
Potters Bar EN6 4BL

DATE: October 2009

SCALE: 1:200

Amendments:

Building Design Consultants
ARCHITECTURAL DESIGNERS
STRUCTURAL ENGINEERS
BUILDING SURVEYORS
PLANNING CONSULTANTS
BUILDING CONSULTANTS

Rear of 1, Hereward Close, Waltham Abbey, Essex EN9 1QP
Tel: 01992 768866 Fax: 01992 768877

THIS WORK MAY BE AFFECTED BY THE PROVISIONS OF THE PARTY WALL ETC ACT 1996

THE CONTRACTOR MAY BE RESPONSIBLE FOR NOTIFYING HSE UNDER CDM REGULATIONS 1994
IF THE PROJECT IS COMMERCIAL OR INDUSTRIAL, A PLANNING SUPERVISOR SHOULD BE APPOINTED.