

## Tree Survey Key

2010/265

<b>Tree No.</b>	Refer to plan
<b>Species</b>	Common name
<b>Age</b>	Y      Young MA      Mid-aged M      Mature OM      Over mature V      Veteran
<b>Height</b>	Estimated to top of crown in metres
<b>DBH</b>	Diameter breast height measured at 1.3 metres above ground, estimated if ivy present on stem
<b>Condition</b>	Brief description of tree
<b>Action</b>	Work proposals
<b>Priority</b>	A      Urgent action required B      Not urgent but implement minor recommendations and monitor C      None re-asses at next survey
<b>Date work completed</b>	Information for records

Survey conducted from the ground, with the use of binoculars where required

Tree Survey		Date: 14/01/09			Location: St Audreys, Old Hatfield		Client: Gascoyne Cecil Estates			
Tree Number	Species	Age	Height m	DBH cm	Condition	Action	Priority	Work completed		
1	Horse Chestnut	MA	17	66	Healthy, vertical fork at 7metres, suckers at base, small broken limb on ground probably from recent snow damage, ivy	Cut ivy	B			
2	Yew	MA	8	33+29	Healthy, forked at ground level	None	C			
3	Sycamore	Y	10	19+18	Healthy, forked at ground level, future limited due to being under the crown of No. 4	Fell	B			
4	Horse Chestnut	OM	19	92	Large tree forked at 1.6 and 3m, ivy, possible rot in crutch obscured by ivy	Cut ivy, closer inspection of crutches, crown reduce by 25%	A			
5	Horse Chestnut	M	16	43	Forked at 1m, competing with No.4, leaning over drive, ivy	Cut ivy, fell or crown reduce	B			
6	Ash	MA	17	46	Hollow, lean over road, poor shape	Fell	A			
7	Horse Chestnut	MA	17	44	Adjacent to No.6 touching at base, lean over road, cavity and rot in base, ivy	Fell	A			
8	Ash	MA	17	46	Lean over road, some deadwood in crown, rooted immediately adjacent to wall, pushing and cracking wall	Fell	A			
9	Beech	M	17	80	Wide crown, triple fork at 4m, right angle limbs in crown, little deadwood, ivy	Inspect crutch for water pockets or rot, cut ivy, shape and reduce crown by 15%	B			
10	Laburnum	OM	14	59	Severe dieback, dropping limbs, but shooting from trunk, ivy	Fell or consider pollarding if trunk is alive and solid, cut ivy	A			
11	Ash	OM	17	62	Rot in part of base, thin crown with deadwood, part over road	Fell	A			
12	Ash	OM	18	61	Thin crown with deadwood, part over road	Fell	A			
13	Ash	OM	20	50	Thin crown with deadwood, part over road	Fell	A			
14	Ash	OM	19	80+	Multi stemmed (6), probably old coppice, rot in base, ivy restricts close inspection, one stem dead with Daldinia concentrica present	Fell	A			
Roadside wall					All trees are growing adjacent too, or within a few metres of the wall, which is retaining the bank on which they are growing. They are pushing the wall out over the road and large cracks are visible	Cut ivy to facilitate inspection, obtain report from structural engineer	A			



**GASCOYNE CECIL  
ESTATES**

Hatfield House, Hatfield, Hertfordshire, AL9 8NQ  
Tel: 01707 287000 Fax: 01707 275719

**Tree Work  
St Audreys Care Home, Hatfield**

SCALE: 1:500 at A3  
DATE: 22/12/2008

MAP FILE REFERENCE:  
Z:\hatfield\staudreys\staudreys\_mdwg.dwg



Produced by Plan Software Services Ltd  
www.plan-software.co.uk  
Based on Ordnance Survey 1:2500 Land Use data with the permission  
of the Controller of Her Majesty's Stationery Office

