

Site Overview




Tree Constraints Plan

(Existing Layout)

Tree Data Schedule

Reference to Schedule	Age & Species	Height (m)	Crown Spread (m)	Notes	Recommendations	View	Annual Value
					Priority	Impact	Retention Category
T1	Early-Mature Pissards Plum <i>Prunus cerasifera</i> 'Pissard'	5	2 x 4.5	Form: Multi-stemmed at 1.5m with an unbalanced crown. No evidence of significant pruning. Defects: Significant decay and emerging gnarled decay brackets to base significant included bark at 1.5m. Other: Acceptable condition at present due to location.	No action required.	Moderate	Low <10 C
T2	Semi-Mature Apple <i>Malus sp.</i>	3.5	1 x 2	Form: Twin-stemmed at 0.5m with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed. Other: Recorded stem diameter is equivalent for 3 stems (14cm, 10cm).	No action required.	Moderate	Low 20-40 C
T3	Semi-Mature Magnolia <i>Magnolia sp.</i>	3.5	0.5 x 4	Form: Multi-stemmed at ground level with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	Moderate	Low 10-20 C
T4	Mature Ash <i>Fraxinus excelsior</i>	15	7 x 6	Position: Situated on third party land. Form: Single stemmed and vertical with a balanced crown. History: Multiple pruning records due to crown reduction. Defects: No significant defects observed. Other: Limited inspection, dimensions estimated.	No action required.	Good	High 40+ A
G5	Semi-Mature Beech <i>Fagus sylvatica</i>	av	av	Form: Two close growing specimens. No evidence of significant pruning. Defects: Symptoms of beech bark disease (bark lesions, die back and exudates) both trees have significant decay columns at 1m within stems.	Remove or reduce height to 5m.	Low	Moderate 10-20 C
T6	Young Beech <i>Fagus sylvatica</i>	4	1.5 x 1	Form: Single stemmed with a slight lean and an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ C
T7	Early-Mature Beech <i>Fagus sylvatica</i>	12	5 x 5	Form: Twin-stemmed at 1.5m with a slightly unbalanced crown. No evidence of significant pruning. Defects: Symptoms of beech bark disease (bark lesions, die back and exudates). Major die back throughout.	Remove.	Low	Very Poor <10 U
G8	Semi-Mature Beech <i>Fagus sylvatica</i>	av	av	Form: Two close growing specimens. No evidence of significant pruning. Defects: Minor die back to upper canopy.	Monitor.	Low	Poor 20-40 C
T9	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	5	2 x 3	Form: Single stemmed and leaning with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 20-40 C
T10	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	6	4 x 4	Position: Situated on third party land. Form: Single stemmed and leaning with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed. Other: Limited inspection, dimensions estimated.	No action required.	High	Good 20-40 C
T11	Early-Mature Lime <i>Tilia sp.</i>	15	4 x 6	Form: Single stemmed and vertical with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed. Other: No prevented detailed inspection.	Remove by and inspect stem for defects.	Moderate	Good 40+ A
T12	Early-Mature Pear <i>Pyrus sp.</i>	3	1.5 x 3	Form: Twin-stemmed at 1m with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed. Other: Smoothed in by.	No action required.	Low	Poor 10-20 C
G13	Semi-Mature Holly <i>Ilex aquifolium</i>	av	av	Form: Two single stemmed specimens. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ C
T14	Early-Mature Purple Beech <i>Fagus sylvatica</i> 'purpurea'	11	1.5 x 5	Form: Single stemmed with a slight lean and an unbalanced crown. No evidence of significant pruning. Defects: Signs of beech bark disease (bark lesions and die back) significant signs of decay to base north and south.	Monitor.	Low	Poor 10-20 C
T15	Mature Oak <i>Quercus robur</i>	17	1.5 x 7	Form: Single stemmed and vertical with a balanced crown. No evidence of significant pruning. Defects: Significant to major deadwood throughout. Tree in decline.	Monitor deadwood monitor.	Low	Poor 20-40 B



Tree Data Schedule Continued

Reference to Schedule	Age & Species	Height (m)	Crown Spread (m)	Notes	Recommendations	View	Annual Value
					Priority	Impact	Retention Category
T16	Early-Mature Ash <i>Fraxinus excelsior</i>	13	6 x 5	Form: Twin-stemmed at ground level with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed. Recorded stem diameter is equivalent for 2 stems (14cm, 10cm).	No action required.	Moderate	Low 40+ B
G17	Early-Mature Lime <i>Tilia sp.</i>	av	av	Form: Two multi-stemmed specimens. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	Good	Fair 40+ A
T18	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	12	4 x 4	Form: Single stemmed and leaning with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 20-40 B-
T19	Semi-Mature Lime <i>Tilia sp.</i>	10	2 x 4	Form: Single stemmed and vertical with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ B
G20	Semi-Mature Cherry <i>Prunus sp.</i>	av	av	Form: Three close growing specimens. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	Moderate	Good 20-40 C
T21	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	12	4 x 3	Form: Single stemmed with a slight lean and an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 20-40 C
T22	Mature Ash <i>Fraxinus excelsior</i>	16	4 x 10	Form: Multi-stemmed at 1m with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	Moderate	Good 40+ A
T23	Early-Mature Sycamore <i>Acer pseudoplatanus</i>	12	4 x 6	Form: Single stemmed and vertical with a balanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ B
T24	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	5	1.5 x 1.5	Form: Multi-stemmed at ground level with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed. Recorded stem diameter is equivalent for 3 stems (12cm, 10cm, 14cm).	No action required.	High	Good 40+ C
T25	Early-Mature Apple <i>Malus sp.</i>	2.5	1.5 x 3	Form: Multi-stemmed at 0.5m with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	Moderate	Fair 10-20 C
T26	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	10	5 x 3.5	Form: Single stemmed and vertical with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ C+
T27	Early-Mature Oak <i>Quercus robur</i>	12	1 x 5	Form: Single stemmed with a slight lean and a slightly unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	Moderate	Good 40+ B
T28	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	12	2 x 3	Form: Twin-stemmed at 1m with an unbalanced crown. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ B
G29	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	av	av	Form: Four close growing specimens. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ B
T30	Early-Mature Oak <i>Quercus robur</i>	10	4 x 8	Form: Single stemmed and vertical with a balanced crown. No evidence of significant pruning. Defects: No prevented detailed inspection.	Remove by and inspect stem for defects.	Moderate	Good 20-40 B
G31	Semi-Mature Sycamore <i>Acer pseudoplatanus</i>	av	av	Form: Two close growing specimens. No evidence of significant pruning. Defects: No significant defects observed.	No action required.	High	Good 40+ C

Tree Ref.	Species	Height (m)	Radius (m)	Area (m²)	Volume (m³)
T1	Pissards Plum	5	5.2	84	9.1
T2	Apple	3.5	2.3	16	4.0
T3	Magnolia	3.5	2.4	18	4.3
T4	Ash	15	10.8	366	19.1
G5	Beech	7.5	3.6	41	6.4
T6	Beech	4	1.7	9	3.0
T7	Beech	12	5.0	79	8.9
G8	Beech	12	4.2	55	7.4
T9	Sycamore	5	2.5	20	4.5
T10	Sycamore	6	2.4	18	4.3
T11	Lime	15	7.2	163	12.8
T12	Pear	3	4.0	50	7.1
G13	Holly	5	2.4	18	4.3
T14	Purple Beech	11	7.0	152	12.3
T15	Oak	17	14.8	684	26.2
T16	Ash	13	8.4	127	11.3
G17	Lime	20	7.8	191	13.8
T18	Sycamore	12	5.3	88	9.4
T19	Lime	10	3.2	33	5.7
G20	Cherry	6	2.4	18	4.3
T21	Sycamore	12	4.8	72	8.5
T22	Ash	16	11.3	400	20.0
T23	Sycamore	12	7.6	180	13.4
T24	Sycamore	5	3.4	35	6.0
T25	Apple	2.5	3.0	28	5.3
T26	Sycamore	10	3.4	35	6.0
T27	Oak	12	6.8	147	12.1
T28	Sycamore	12	5.2	84	9.1
G29	Sycamore	12	5.4	92	9.6
T30	Oak	10	7.7	185	13.6
G31	Sycamore	10	3.0	28	5.3

Tree Constraints Plan

Drawing No: CCL 10561 / TCP Rev 2

Title: Tree Constraints Plan (Existing Layout)

Site: Land adjacent to 38 The Ridgeway EN6 4AX

Scale: 1:300 Paper Size: A1

Tree Retention Categories

- Category A tree
- Category B tree
- Category C tree
- Category U tree

Trees of high quality with an estimated life expectancy of 40+ years. Usually large trees with significant presence or smaller trees with excellent form. Retention of these trees is highly desirable.

Trees of moderate quality with a life expectancy of 20+ years. Usually maturing trees, or younger trees with good form. Retention of these trees is desirable though less than Category A trees.

Unremarkable trees of low quality and merit. Individual specimens are not considered to be a material planning consideration.

Trees unsuitable for retention due to their very poor condition.

BS s837 Root Protection Area (radius = 1xstem diameter)

Root Protection Area needing amendment due to site conditions, e.g. presence of existing road or building.

Root Protection Area having been amended to account for site conditions.

T1 = Tree No 1 G2 = Group No 2 H3 = Hedge No 3

Photo 1

MN = Measured North: Canopy spreads are sometimes measured to an approximate N defined by site features. Often more accurate, especially where rows of trees are not aligned N/S or E/W.

Excerpts from the Arboricultural Impact Assessment

Overview

It is proposed to construct a new detached residential property and garage as indicated on the plans in Appendix 6. The existing layout is indicated in black and the footprint of the proposed layout is indicated in pale green.

A new vehicular access is to be created from The Ridgeway. The table below summarises the potential impact on trees due to various activities.

Activity	Trees Potentially Affected
Tree Removal: Retention Category A	None
Tree Removal: Retention Category B	T16
Tree Removal: Retention Category C	T1, T2, T3, G5, T6, G8, T9, T12, G13, T14 and the 4m tall dense holly and laurel.
Tree Removal: Retention Category U	T6
Tree Pruning	T11 and G7
RPA House Foundations	T15, G7 and T10
RPA Terrace Foundations	T15, G7 and T10
RPA New Hard Surface	T4
RPA Replace Existing Hard Surface	None
RPA Underground Services	Unknown - To be confirmed
RPA Change of Ground Levels	None
RPA Soil Compaction	Trees adjacent the construction area (preventable by installing tree protection measures)

Other potentially damaging activities often associated with construction sites include demolition or the careless use of plant machinery, hazardous materials, or fires. All of the above potential impacts are considered in detail throughout this section.

The accompanying Arboricultural Method Statement (duplicated in Appendix 6) specifies the measures proposed to minimise all possible potential risks of damage to the retained trees.

Tree Removal

All trees to be removed are indicated on the Tree Removal Plan and are listed below:

- Retention Category A:** It is proposed to retain all Retention Category A trees.
- Retention Category B:** It is proposed to remove the Retention Category B tree, T16. This tree is located so close to the proposed residence that its retention is not possible. This tree grows in excess of 3m from the closest public vantage point and also grows within a row of trees with a similar height. Consequently, it is barely visible from public vantage points and it is not considered to have a particularly high amenity value. Its removal shall not have a major impact on the visual amenity of the locality.
- Retention Category C:** It is proposed to remove the following Retention Category C trees: T1, T2, T3, G5, T6, G8, T9, T12, G13, T14 and the 4m tall dense holly and laurel. These trees are wither located so close to the proposed residence that their retention is not practical, or they are of low/poor quality and their replacement is desired. The majority of these trees are relatively small and are barely visible from public vantage points. Consequently, they are not considered to have a particularly high amenity value and their removal shall not have a significant impact on the visual amenity of the locality.
- Retention Category U:** It is proposed to remove the Retention Category U tree, T7. Trees within this category are in such poor condition that they should be removed regardless of development proposals. Consequently, the removal of Category U trees is not considered to be a direct impact of the development.



Details specific to each tree can also be found in the Tree Data Schedule.

Mitigation Planting

There is ample scope for new planting to mitigate against tree loss. I understand that it is proposed to plant several new trees as part of a post development landscaping scheme.

See Section 4 for a more detailed assessment

Proposed Layout (Pale Green)



Tree Removal Plan

(Existing Layout with Proposals Overlaid)

Tree Ref.	Species	Height (m)	Root Protection Area		
			Radius (m)	Square (m)	
T1	Pissards Plum	5	5.2	84	9.1
T2	Apple	3.5	2.3	16	4.0
T3	Magnolia	3.5	2.4	18	4.3
T4	Ash	15	10.8	366	19.1
G5	Beech	7.5	3.6	41	6.4
T6	Beech	4	1.7	9	3.0
T7	Beech	12	5.0	79	8.9
G8	Beech	12	4.2	55	7.4
T9	Sycamore	5	2.5	20	4.5
T10	Sycamore	6	2.4	18	4.3
T11	Lime	15	7.2	163	12.8
T12	Pear	3	4.0	50	7.1
T13	Holly	5	2.4	18	4.3
T14	Purple Beech	11	7.0	152	12.3
T15	Oak	17	14.8	684	26.2
T16	Ash	13	6.4	127	11.3
G17	Lime	20	7.8	191	13.8
T18	Sycamore	12	5.3	88	9.4
T19	Lime	10	3.2	33	5.7
G20	Cherry	6	2.4	18	4.3
T21	Sycamore	12	4.8	72	8.5
T22	Ash	16	11.3	400	20.0
T23	Sycamore	12	7.6	180	13.4
T24	Sycamore	5	3.4	35	6.0
T25	Apple	2.5	3.0	28	5.3
T26	Sycamore	10	3.4	35	6.0
T27	Oak	12	6.8	147	12.1
T28	Sycamore	12	5.2	84	9.1
G29	Sycamore	12	5.4	92	9.6
T30	Oak	10	7.7	185	13.6
G31	Sycamore	10	3.0	28	5.3

Drawing No: CCL 10561 / TRP Rev: 1

Title: Tree Removal Plan (Existing Layout with Proposals Overlaid)

Site: Land adjacent to 38 The Ridgeway EN6 4AX

Scale: 1:300 Paper Size: A1



Tree Retention Categories

Stems & canopies shown

Category A tree

Category B tree

Category C tree

Category U tree

Trees of high quality with an estimated life expectancy of 40+ years. Usually large trees with significant presence or smaller trees with excellent form. Retention of these trees is highly desirable.

Trees of moderate quality with a life expectancy of 20+ years. Usually maturing trees or younger trees with good form. Retention of these trees is desirable though less than Category A trees.

Unremarkable trees of low quality and merit. Individual specimens are not considered to be a material planning consideration.

Trees unsuitable for retention due to their very poor condition.

Tree Removal Plan

(Existing Layout with Proposals Overlaid)

BS 5837 Root Protection Area (radius = 1xstem diameter)

Root Protection Area needing amendment due to site conditions, e.g. presence of existing road or building.

Root Protection Area having been amended to account for site conditions

T1 = Tree No 1 G2 = Group No 2 H3 = Hedge No 3

Tree to be removed to facilitate the proposal

Tree to be removed due to its low quality

Proposed pruning

MN = Measured North

Canopy spreads are sometimes measured to an approximate N defined by site features.

Often more accurate, especially where rows of trees are not aligned N-S or E-W.

Excerpts from the Arboricultural Impact Assessment

Overview
It is proposed to construct a new detached residential property and garage as indicated on the plans in Appendix 6. The existing layout is indicated in black and the footprint of the proposed layout is indicated in pale green.

A new vehicular access is to be created from The Ridgeway.
The table below summarises the potential impact on trees due to various activities.

Activity	Trees Potentially Affected
Tree Removal: Retention Category A	None
Tree Removal: Retention Category B	T16
Tree Removal: Retention Category C	T1, T2, T3, C5, T6, G8, T9, T12, G15, T14 and the 4m tall dense holly and laurel.
Tree Removal: Retention Category U	T6
Tree Pruning	T11 and G17
RPA: House Foundations	T15, G17 and T10
RPA: Terrace Foundations	T15, G17 and T10
RPA: New Hard Surface	T4
RPA: Replace Existing Hard Surface	None
RPA: Underground Services	Unknown - To be confirmed
RPA: Change of Ground Levels	None
RPA: Soil Compaction	Trees adjacent the construction area (preventable by installing tree protection measures)

Other potentially damaging activities often associated with construction sites include demolition or the careless use of plant machinery, hazardous materials, or fires. All of the above potential impacts are considered in detail throughout this section.
The accompanying Arboricultural Method Statement (duplicated in Appendix 6) specifies the measures proposed to minimise all possible potential risks of damage to the retained trees.
Impact on Tree Canopies
It is proposed to prune back the lower branches of T11 and G17 that are growing towards the proposal in order to create a clearance distance of 2.5m. This shall require the removal of relatively small secondary branches which should be pruned back to a secondary growth point. The pruning works should be undertaken sympathetically (working to BS 3998: 2010 guidelines).
Such a small amount of pruning shall have no impact on local visual amenity and shall not be detrimental to tree health.
All other tree canopies shall be unaffected by the proposals.

Impact on Tree Roots
Building Foundations:
The foundations for the new property will extend into the very edge of the theoretical Root Protection Areas of T15, G17 and T10. However, only circa 2%, 1.5% and 1% of the Root Protection Areas shall be affected respectively (see the Impact Assessment Plan), so the potential impact is considered to be negligible.
However, in order to minimise the impact on tree roots, a pile and beam or pile and raft foundation is proposed where the building shall extend into the theoretical Root Protection Areas. The following restrictions are proposed:
• Excavation shall be limited to a maximum depth of 400mm to facilitate the installation of a raft or beam foundation.
• Only hand tools shall be used during the excavation.
• If roots in excess of 25mm diameter are encountered close to the edge of the excavation, they shall be retained wherever possible and protected with damp sacking during times that they are unearthed. Any roots that need to be severed shall be pruned with secateurs.
• The raft/beam may be supported on narrow diameter piles (maximum diameter 300mm). Before installing such piles, their location shall be determined by trial pits excavated to a depth of 600mm using hand tools and overseen by the appointed arborist. Trial pit dimensions should not exceed 300mm x 300mm. If any roots in excess of 25mm diameter are encountered, the pile shall be relocated.

Terrace Foundations:
The foundations for the new terrace will extend into the very edge of the theoretical Root Protection Areas of T15, G17 and T10. Timber decking is proposed for the terrace and the following restrictions are proposed:
• Post holes shall be narrow as possible and shall not exceed 300mm x 300mm.
• Excavation for the post holes shall be undertaken using hand tools and overseen by the local authority tree officer or an approved project arborist.
• Roots in excess of 25mm are to be retained and the post hole relocated.
• A flexible fencing system which permits the relocation of the posts will therefore be necessary.
• All exposed roots over 25mm diameter shall be sleeved to prevent contact with fence posts and cement products.
By adopting such a sympathetic method of installation, it will be possible to retain all significant roots and ensure that the root system will be able to supply the canopy with the required water and nutrients. Hence it is considered that the proposed terrace shall not result in any long-term detrimental impact on the health of T15, G17 and T10.

New Surfaces:
It is proposed to install a new driveway over the Root Protection Area of T4. Although the full extent of the driveway has not yet been confirmed, it shall need to be installed in a sympathetic manner to minimise excavation and compaction of soils. Guidelines are discussed below and proposed in the accompanying Arboricultural Method Statement, which will minimise any impacts on roots.
In order to minimise the impact on roots where the new driveway is proposed over the Root Protection Area of T4, the following mitigation is proposed:
• A suitable load spreading surface shall be in place at all times during demolition and construction activities.
• The new surface shall be installed entirely above ground. Any existing turf or vegetation may be removed along with very loose topsoil. However no further excavation shall occur.
• A gravel sub-base containing no fine particles shall be incorporated into the design. This shall be contained within a 3D cellular confinement system to ensure that the weight of vehicles will be evenly spread over a wide area. This shall prevent excessive soil compaction and reduce the depth of sub-base required.
• A porous surface and sub-base are proposed which will enable passage of oxygen and water to the soils beneath.
• The new surface shall be located in excess of 0.5m from any buttress roots as recommended in BS 5837 (7.4.2.7).

Underground Services:
No underground services should be installed through any Root Protection Area without consulting the project arborist and if necessary, gaining approval from the local authority.
Summary
In order to facilitate the development, it is proposed to remove one Retention Category B tree and thirteen Retention Category C and Retention Category U trees, which are all located internally to the site, the majority of these trees are relatively small and barely visible from public vantage points. Consequently, there shall not be a significant impact on local amenity due to their removal. Several new trees are to be planted to mitigate against tree removal and to ensure tree cover is maintained throughout the site.
T11 and G17 require minimal pruning to create an adequate clearance from the proposal.
A new hard surface is proposed within the RPA of T4. However, a porous surface is proposed using the No-Dig Method as per BS 5837 recommendations. Consequently, the impact on T4 shall be minimal.
Foundations for the new building and terraced area are proposed within the Root Protection Area of T15, G17 and T10. However, the small extent of the RPAs affected coupled with the sympathetic foundation design, shall ensure no detrimental impact on trees.
A suitable load spreading surface shall need to be maintained throughout the Restricted Activity Zones A.
Tree protection measures are specified throughout the accompanying Arboricultural Method Statement that will ensure no negative impact on retained trees due to construction activity.
Adequate space has been allowed between the proposal and all trees such that no future pressure to over-prune or remove trees shall occur as a consequence of the proposal.

See Section 4 for a more detailed assessment

Proposed Layout (Pale Green)

Dense overgrown mixed species including Hawthorn, Sycamore and Holly
Ht: 4m
Dia: 20cm

Dense overgrown mixed species including Hawthorn, Sycamore and Holly
Ht: 4m
Dia: 20cm

Mixed shrubs
Ht: 3m

Dense Holly and Laurel
Ht: 4m

Dense Holly and Laurel
Ht: 4m

It is proposed to prune back the lower branches of T11 and G17 that are growing towards the proposal in order to create a clearance distance of 2.5m. This shall require the removal of relatively small secondary branches which should be pruned back to a secondary growth point.
Such a small amount of pruning shall have no impact on local visual amenity and shall not be detrimental to tree health.

It is proposed to install a new driveway over the Root Protection Area of T4. Although the full extent of the driveway has not yet been confirmed, it shall need to be installed in a sympathetic manner to minimise excavation and compaction of soils. Guidelines are discussed below and proposed in the accompanying Arboricultural Method Statement, which will minimise any impacts on roots.

In order to minimise the impact on roots where the new driveway is proposed over the Root Protection Area of T4, the following mitigation is proposed:
• A suitable load spreading surface shall be in place at all times during demolition and construction activities.
• The new surface shall be installed entirely above ground. Any existing turf or vegetation may be removed along with very loose topsoil. However no further excavation shall occur.
• A gravel sub-base containing no fine particles shall be incorporated into the design. This shall be contained within a 3D cellular confinement system to ensure that the weight of vehicles will be evenly spread over a wide area. This shall prevent excessive soil compaction and reduce the depth of sub-base required.
• A porous surface and sub-base are proposed which will enable passage of oxygen and water to the soils beneath.
• The new surface shall be located in excess of 0.5m from any buttress roots as recommended in BS 5837 (7.4.2.7).

The foundations for the new terrace will extend into to the very edge of the theoretical Root Protection Areas of T15, G17 and T10. Timber decking is proposed for the terrace and the following restrictions are proposed:
• Post holes shall be narrow as possible and shall not exceed 300mm x 300mm.
• Excavation for the post holes shall be undertaken using hand tools and overseen by the local authority tree officer or an approved project arborist.
• Roots in excess of 25mm are to be retained and the post hole relocated.
• A flexible fencing system which permits the relocation of the posts will therefore be necessary.
• All exposed roots over 25mm diameter shall be sleeved to prevent contact with fence posts and cement products.
By adopting such a sympathetic method of installation, it will be possible to retain all significant roots and ensure that the root system will be able to supply the canopy with the required water and nutrients. Hence it is considered that the proposed terrace shall not result in any long-term detrimental impact on the health of T15, G17 and T10.

The foundations for the new property will extend into to the very edge of the theoretical Root Protection Areas of T15, G17 and T10. However, only circa 2%, 1.5% and 1% of the Root Protection Areas shall be affected respectively, so the potential impact is considered to be negligible.

However, in order to minimise the impact on tree roots, a pile and beam or pile and raft foundation is proposed where the building shall extend into the theoretical Root Protection Areas. The following restrictions are proposed:
• Excavation shall be limited to a maximum depth of 400mm to facilitate the installation of a raft or beam foundation.
• Only hand tools shall be used during the excavation.
• If roots in excess of 25mm diameter are encountered close to the edge of the excavation, they shall be retained wherever possible and protected with damp sacking during times that they are unearthed. Any roots that need to be severed shall be pruned with secateurs.
• The raft/beam may be supported on narrow diameter piles (maximum diameter 300mm). Before installing such piles, their location shall be determined by trial pits excavated to a depth of 600mm using hand tools and overseen by the appointed arborist. Trial pit dimensions should not exceed 300mm x 300mm. If any roots in excess of 25mm diameter are encountered, the pile shall be relocated.


Drawing No:	CCL 10561 / TRP Rev: 1
Title:	Tree Removal Plan (Existing Layout with Proposals Overlaid)
Site:	Land adjacent to 38 The Ridgeway ENE 4AX
Scale:	1:300
Paper Size:	A1

Tree Retention Categories	Stems & canopies shown
Category A tree	
Category B tree	
Category C tree	
Category U tree	

Trees of high quality with an estimated life expectancy of 40+ years. Usually large trees with significant presence or smaller trees with excellent form. Retention of these trees is highly desirable.
Trees of moderate quality with a life expectancy of 20+ years. Usually maturing trees, or younger trees with good form. Retention of these trees is desirable though less than Category A trees.
Unremarkable trees of low quality and merit. Individual specimens are not considered to be a material planning consideration.
Trees unsuitable for retention due to their very poor condition.

Impact Assessment Plan

(Existing Layout with Proposals Overlaid)



Impact Assessment Plan

(Existing Layout with Proposals Overlaid)

Tree Ref.	Species	Height (m)	Root Protection Area		
			Radius (m)	Area (m ²)	
T1	Pissards Plum	5	5.2	84	9.1
T2	Apple	3.5	2.3	16	4.0
T3	Magnolia	3.5	2.4	18	4.3
T4	Ash	15	10.8	366	19.1
G5	Beech	7.5	3.6	41	6.4
T6	Beech	4	1.7	9	3.0
T7	Beech	12	5.0	79	8.9
G8	Beech	12	4.2	55	7.4
T9	Sycamore	5	2.5	20	4.5
T10	Sycamore	6	2.4	18	4.3
T11	Lime	15	7.2	163	12.8
T12	Pear	3	4.0	50	7.1
G13	Holly	5	2.4	18	4.3
T14	Purple Beech	11	7.0	152	12.3
T15	Oak	17	14.8	684	26.2
T16	Ash	13	6.4	127	11.3
G17	Lime	20	7.8	191	13.8
T18	Sycamore	12	5.3	88	9.4
T19	Lime	10	3.2	33	5.7
G20	Cherry	6	2.4	18	4.3
T21	Sycamore	12	4.8	72	8.5
T22	Ash	16	11.3	400	20.0
T23	Sycamore	12	7.6	180	13.4
T24	Sycamore	5	3.4	35	6.0
T25	Apple	2.5	3.0	28	5.3
T26	Sycamore	10	3.4	35	6.0
T27	Oak	12	6.8	147	12.1
T28	Sycamore	5.2	5.2	84	9.1
G29	Sycamore	12	5.4	92	9.6
T30	Oak	10	7.7	185	13.6
G31	Sycamore	10	3.0	28	5.3

BS 5837 Root Protection Area (radius = 1xstem diameter)

Root Protection Area needing amendment due to site conditions, e.g. presence of existing road or building.

Root Protection Area having been amended to account for site conditions

T1 = Tree No 1 G2 = Group No 2 H3 = Hedge No 3

Tree to be removed to facilitate the proposal for site conditions

Tree to be removed due to its low quality

Proposed pruning

MN = Measured North: Canopy spreads are sometimes measured to an approximate N defined by site features. Often more accurate, especially where rows of trees are not aligned N/S or E/W.

