

**Plot 5000, Hatfield Business Park
Soft Schedules**

Document ref 1178-SH-05

-	Issued for BREEAM Information	20.03.2017
A	Issued for Planning	24.03.2017

Macgregor Smith Ltd,
Christopher House, 11-12 High Street, Bath BA1 5AQ
Tel: 01225 464690, Fax: 01225 429962
Email: enquires@macgregorsmith.co.uk

Macgregor - Smith
Landscape Architecture



Plot 5000
Hatfield Business Park
Soft Schedules - Trees

Variety	Code	Overall Height/Girth cm	English Description	Clear Stem (C/S) Feathered (F)	Notes
Alnus glutinosa	4x	20-25cm	Semi mature	C/S	Rootballed
Betula pendula	3x	3.0-3.5m height	Multi stemmed	M/S	Containerised
Prunus 'Accolade'	4x	3.0-3.5m height	Multi stemmed	MS	Rootballed
Prunus avium 'Plena'	5x	25-30cm	Semi mature	C/S	Rootballed

Plot 5000
Hatfield Business Park
Soft Schedules - Hedges

Ornamental Hedging Species						
Variety	Size	Height/ Spread cm	Habit	Minimum no. of breaks in lower third	Planting density per linear metre	Notes
Carpinus betulus	10L pot	0.9-1.2m height	Branched	10	5 / linear metre in a double staggered row	Well feathered to base
Prunus lusitanica	10L pot	0.9-1.2m height	Branched	10	5 / linear metre in a double staggered row	Well feathered to base

Plot 5000
Hatfield Business Park
Soft Schedules - Hedges

Native Hedging Species						
Variety	Size	Height/ Spread cm	Habit	Minimum no. of breaks in lower third	Planting density per linear metre	Notes
Crataegus monogyna	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	
Cornus stolonifera	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	
Corylus avellana	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	
Ilex aquifolium	3L pot	30-45cm	Bushy	8	4.5 no. per linear metre	
Prunus spinosa	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	
Rosa canina	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	
Sambucus nigra	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	
Viburnum opulus	3L pot	45-60cm	Bushy	8	4.5 no. per linear metre	

Plot 5000
Hatfield Business Park
Soft Schedules - Shrubs

Container Grown Shrubs, Grasses and Herbaceous Perennials Specification List						
Variety	Pot Size	Height/Spread	Habit	Min no of breaks in lower third	Planting Density per m²	Notes
Amelanchier canadensis	25L	1.0-1.2m	Bushy	15	as shown	
Asplenium scolopendrium	2L	-	Bushy	-	8	Full Pot, fully rooted, healthy clump
Carex testacea	3L	30-45cm	Bushy		4	Well rooted clump
Cornus sericea 'Kelsey'	3L	30-45cm	Bushy		4	
Cornus alba 'Westonbirt'	3L	30-45cm	Bushy		3	
Cornus 'Mid Winter Fire'	5L	45-60cm	Branched	8	3	
Crocosmia 'Carmine Brilliant'	3L				7	
Hebe 'Pluto of Golden Esk'	3L	30/45cm			5	
Liriope 'Big Blue'	3L	15-30cm			6	Well rooted clump
Luzula sylvatica	3L	30-45cm			8	Well rooted clump
Photinia 'Red Robin'	3L	60-90cm	Branched	8	2.5	
Polystichum setiferum	3L	20-30cm			4	
Prunus 'Low 'n' Green'	3L	30-45cm	Branched	8	3	
Prunus lusitanica	3L	30-45cm	Branched	8	2.5	
Prunus zabeliana	3L	30-45cm	Branched	8	3	
Rosa 'Kent'	3L	45/60cm	Branched	8	3.5	

Plot 5000
Hatfield Business Park
Soft Schedules - Shrubs

Container Grown Shrubs, Grasses and Herbaceous Perennials Specification List						
Salvia 'May Night'	3L	20-30cm			6	Well rooted clump
Sesleria autumnalis	3L	20-30cm			5	Well rooted clump