

Mix 1		
Anemone x hybrida 'September Charm'	25%	2L @ 5 plants per m ²
Cornus sanguinea 'Midwinter Fire'	30%	3L @ 4 plants per m ²
Lonicera pileata	20%	3L @ 3 plants per m ²
Persicaria bistorta 'Superba'	10%	2L @ 5 plants per m ²
Polystichum setiferum	15%	2L @ 5 plants per m ²

Mix 2		
Anemone x hybrida 'September Charm'	10%	2L @ 5 plants per m ²
Asplenium scolopendrium	5%	2L @ 7 plants per m ²
Carex testacea	15%	3L @ 5 plants per m ²
Hebe 'Watson's Pink'	10%	3L @ 5 plants per m ²
Liriope muscari 'Big Blue'	10%	2L @ 6 plants per m ²
Lonicera pileata	10%	3L @ 4 plants per m ²
Miscanthus 'Starlight'	10%	2L @ 5 plants per m ²
Philomis tuberosa 'Amazone'	-	Specimen plants
Persicaria bistorta 'Superba'	5%	2L @ 5 plants per m ²
Polystichum setiferum	-	Specimen plants
Sanguisorba menziesii	-	Specimen plants
Sedum 'Matrona'	5%	2L @ 8 plants per m ²
Sesleria autumnalis	15%	2L @ 6 plants per m ²

Mix 3		
Sedum 'Matrona'	20%	2L @ 8 plants per m ² interplanted
Sesleria autumnalis	80%	2L @ 6 plants per m ²

Sedum to be interplanted evenly through the Sesleria autumnalis

Mix 4		
Anemone x hybrida 'September Charm'	30%	2L @ 5 plants per m ²
Asplenium scolopendrium	10%	2L @ 7 plants per m ²
Astrantia 'Claref'	-	Specimen plants
Persicaria bistorta 'Superba'	10%	2L @ 5 plants per m ²
Polystichum setiferum	10%	2L @ 5 plants per m ²
Sedum 'Matrona'	10%	2L @ 8 plants per m ²
Sesleria autumnalis	30%	2L @ 6 plants per m ²

Mix 5		
Anemone x hybrida 'September Charm'	-	Specimen plants
Astrantia 'Claref'	-	Specimen plants
Carex Testacea	35%	3L @ 5 plants per m ²
Persicaria bistorta 'Superba'	15%	2L @ 5 plants per m ²
Polystichum setiferum	-	Specimen plants
Sedum 'Matrona'	15%	2L @ 8 plants per m ²
Sesleria autumnalis	35%	2L @ 6 plants per m ²

Mix 6		
Astrantia 'Claref'	-	Specimen plants
Polystichum setiferum	-	Specimen plants
Sedum 'Matrona'	20%	2L @ 8 plants per m ²
Sanguisorba menziesii	-	2L Specimen plants
Sesleria autumnalis	80%	2L @ 6 plants per m ²

Sedum to be interplanted evenly through the Sesleria autumnalis

Mix 7		
Anemone x hybrida 'September Charm'	10%	2L @ 5 plants per m ²
Asplenium scolopendrium	5%	2L @ 7 plants per m ²
Astrantia 'Claref'	-	Specimen plants
Carex testacea	12.5%	3L @ 5 plants per m ²
Cornus sanguinea 'Midwinter Fire'	2.5%	3L @ 4 plants per m ²
Digitalis ferruginea	-	Specimen plants
Euphorbia amygdaloides var robbiae	5%	2L @ 7 plants per m ²
Hebe 'Watson's Pink'	5%	3L @ 5 plants per m ²
Liriope grandiflora	5%	
Liriope muscari 'Big Blue'	10%	2L @ 6 plants per m ²
Lonicera pileata	10%	3L @ 4 plants per m ²
Miscanthus 'Starlight'	10%	2L @ 5 plants per m ²
Philomis tuberosa 'Amazone'	-	Specimen plants
Persicaria bistorta 'Superba'	5%	2L @ 5 plants per m ²
Polystichum setiferum	-	Specimen plants
Sanguisorba menziesii	-	Specimen plants
Sedum 'Matrona'	5%	2L @ 8 plants per m ²
Sesleria autumnalis	15%	2L @ 6 plants per m ²

KEY

- Existing trees to be retained
Refer to vegetation retention and removal plan 1226-003 for details
- Existing trees to be removed
Refer to vegetation retention and removal plan 1226-003 for details
- Proposed trees to boundary
Semi-mature, 30-45cm girth
- Proposed trees to car park
Semi-mature, 30-45cm girth
- Proposed multi-stem trees
Multi-stem, 2.0-2.5m height
- Feature hedge to wall
Clipped Columns, 6m height
- Proposed groundcover planting
- Existing grass to verges
- Proposed amenity grass
Tillers 'Arend' turf



Revision	Description	Drawn by	Checked by	Date
-	For Comment	KM	RG	22.02.19

0 5m 10m 20m



Macgregor • Smith
Landscape Architecture

project	Hatfield Plot 5100 H R Owen	drawn by	KM
status	For Comment	checked by	RG
title	Planting Plan 2 of 2	date	14.02.19
Xref	2018-22 S-100 Ground Floor Site Plan.dwg; 15559C_T_REV 1	scale	1:250@a1
drawing No	1226-202	revision	-