









**KEY**

-  **Existing Trees To Be Retained**  
Refer to vegetation retention and removal plan 1226-003 for details
-  **Existing Lawn To Be Retained**
-  **Proposed Deciduous Clear Stem Trees**
-  **Proposed Coniferous Clear Stem Trees**
-  **Proposed Multistem Trees**
-  **Feature hedge to wall**  
Clipped Columns, 3m height
-  **Proposed Shrub Planting**
-  **Proposed Amenity Turf**  
Tillers 'Arend' turf

- Mix 1 - West Boundary**
- Sesleria autumnalis 60% 2L@ 6 plants per m<sup>2</sup>
  - Salvia nemorosa 'Caradonna' 25% 2L@ 6 plants per m<sup>2</sup>
  - Sedum 'Matrona' 15% 2L@ 8 plants per m<sup>2</sup>

- Mix 2a - West Frontage**
- Anemathelle lessoniana 20% 2L@ 5 plants per m<sup>2</sup>
  - Carex testacea 15% 3L@ 5 plants per m<sup>2</sup>
  - Hydrangea 'Limelight' - 15L specimens
  - Liriope muscari 'Big Blue' 10% 2L@ 7 plants per m<sup>2</sup>
  - Pinus mugo 'Mughus' - 0.75m wide specimens
  - Polystichum setiferum 5% 2L@ 5 plants per m<sup>2</sup>
  - Sarcococca 'Winter Gem' 25% 2L@ 3 plants per m<sup>2</sup>
  - Sarcococca 'Winter Gem' - 15L specimens
  - Sesleria autumnalis 25% 2L@ 6 plants per m<sup>2</sup>

- Mix 2b - West Frontage**
- Anemathelle lessoniana 20% 2L@ 5 plants per m<sup>2</sup>
  - Anemone 'Honorine Jobert' 10% 2L Specimen plants
  - Calamagrostis 'Karl Foerster' 12.5% 2L@ 5 plants per m<sup>2</sup>
  - Carex testacea 12.5% 3L@ 5 plants per m<sup>2</sup>
  - Hydrangea 'Limelight' - 15L specimens
  - Liriope muscari 'Big Blue' 10% 2L@ 7 plants per m<sup>2</sup>
  - Pinus mugo 'Mughus' - 0.75m wide specimens
  - Polystichum setiferum 5% 2L@ 5 plants per m<sup>2</sup>
  - Sarcococca 'Winter Gem' 20% 2L@ 3 plants per m<sup>2</sup>
  - Sarcococca 'Winter Gem' - 15L specimens
  - Sesleria autumnalis 10% 2L@ 6 plants per m<sup>2</sup>

- Mix 3 - Main Entrance frontage**
- Anemone 'Honorine Jobert' 10% 2L Specimen plants
  - Calamagrostis 'Karl Foerster' 10% 2L@ 5 plants per m<sup>2</sup>
  - Carex testacea 10% 3L@ 5 plants per m<sup>2</sup>
  - Cornus sanguinea 'Midwinter Fire' 5% 3L@ 4 plants per m<sup>2</sup>
  - Hydrangea 'Limelight' - 15L specimens
  - Liriope muscari 'Big Blue' 10% 2L@ 7 plants per m<sup>2</sup>
  - Molinia 'Transparent' - 5L specimens
  - Pinus mugo 'Mughus' - 0.75m wide specimens
  - Polystichum setiferum 5% 2L@ 5 plants per m<sup>2</sup>
  - Prunus 'Low 'n' Green' 5% 2L@ 3 plants per m<sup>2</sup>
  - Pyracantha 'Red Cushion' 5% 2L@ 3 plants per m<sup>2</sup>
  - Salvia 'Caradonna' 10% 2L@ 6 plants per m<sup>2</sup>
  - Sarcococca 'Winter Gem' 10% 2L@ 3 plants per m<sup>2</sup>
  - Sesleria autumnalis 10% 2L@ 6 plants per m<sup>2</sup>
  - Sedum 'Matrona' 10% 2L@ 8 plants per m<sup>2</sup>

- Mix 4 - Building frontage**
- Veronicastrum 'Lavendelturm' 20% 2L@4/linear m
  - Sesleria autumnalis 80% 2L@ 6 plants per m<sup>2</sup>

- Mix 5 - Statement beds**
- Anemathelle lessoniana 15% 2L@ 5 plants per m<sup>2</sup>
  - Ilex crenata - 90cm Ø clipped dome
  - Molinia 'Transparent' - 5L specimens
  - Pinus mugo 'Mughus' - 0.75m wide specimens
  - Sesleria autumnalis 55% 2L@ 5 plants per m<sup>2</sup>
  - Salvia 'Caradonna' 15% 2L@ 6 plants per m<sup>2</sup>
  - Sedum 'Matrona' 15% 2L@ 8 plants per m<sup>2</sup>


- Mix 6 - CP statement**
- Sesleria autumnalis 100% 2L@ 6 plants per m<sup>2</sup>
  - Pinus mugo 'Mughus' - 0.75m wide specimens

- Mix 7 - CP beds**
- Anemathelle lessoniana 15% 2L@ 5 plants per m<sup>2</sup>
  - Ilex crenata - 90cm Ø clipped dome
  - Pinus mugo 'Mughus' - 5L specimens
  - Sesleria autumnalis 55% 2L@ 5 plants per m<sup>2</sup>
  - Salvia 'Caradonna' 15% 2L@ 6 plants per m<sup>2</sup>
  - Sedum 'Matrona' 15% 2L@ 8 plants per m<sup>2</sup>

- Mix 8 - East frontage**
- Calamagrostis 'Karl Foerster' 15% 2L@ 5 plants per m<sup>2</sup>
  - Carex testacea 15% 3L@ 5 plants per m<sup>2</sup>
  - Cornus sanguinea 'Midwinter Fire' 10% 3L@ 4 plants per m<sup>2</sup>
  - Liriope muscari 'Big Blue' 15% 2L@ 6 plants per m<sup>2</sup>
  - Prunus 'Low 'n' Green' 15% 3L@ 3 plants per m<sup>2</sup>
  - Rosa 'Kent' 15% 3L@ 3.5 plants per m<sup>2</sup>
  - Sarcococca 'Winter Gem' - 15L specimens
  - Sesleria autumnalis 10% 2L@ 6 plants per m<sup>2</sup>



Revision	Description	Drawn by	Checked by	Date
-	For Comment	KM	RG	22.02.19
A	Updated to revised site layout	AL	RG	12.09.19
B	Updated for NMA application	JW	SL	07.12.20
C	NMA application	JR	SL	16.12.20
D	NMA application	JR	SL	18.12.20
E	NMA application	KM	SL	29.04.21



**Macgregor • Smith**  
Landscape Architecture

project	Hatfield Plot 5000A H R Owen	drawn by	KM
status	Updated for NMA application	checked by	RG
title	Planting Plan 1 of 2	date	14.02.19
Xref	xref	scale	1:250@a1
drawing No	1226-201	revision	E