

DESCRIPTION

Bi-Folding door set, manufactured using Accoya with a Sapele.
 Doors to be a 3/4 configuration with the pass door being hung on parliament hinges to fold flat to the wall. Pass door to be fitted with multipoint locking and Stainless steel handle set.
 Supplied fully glazed with 24mm 4-16-4 argon filled toughened glass units, with applied bars as per the attached drawings.

Rev.	Notes	Revision Date
Ironmongery Items		
0	0	0
0	0	0
0	0	0
0	0	0
0	0	0
0	0	0
0	0	0

Job no: 32041
 Client: Mr C Eaton
 Title: 24 Church Street, Old Hatfield
 Dwg no: 23041.01 Drawn: C Chapman
 Scale: 1:1 @ A3 Date: 21-04-2017

BARRJOINERY

WINDOWS . DOORS . CABINERY

Unit 10 Field Farm info@barrjoinery.co.uk
 North Weston, Thame 01844 217706
 Oxen, OX9 2HQ www.barrjoinery.co.uk

Name: _____
 Signed: _____
 Date: _____

