




Front Elevation



Side Elevation



Rear Elevation



Side Elevation

The Town & Country Planning (General Permitted Development) Order 1995 (as amended in 2008, 2013 & 2014) Part 1 of schedule 2 sets out the laws concerning permitted development for householders.

Class E
This provides permitted development rights within the area surrounding a house for:

- a) any building or enclosure, swimming or any other pool, required for a use incidental to the enjoyment of the dwelling house as such (this includes personal enjoyment of the occupants of the dwelling,) and for the maintenance, improvement or other alteration of such a building or enclosure

OR
b) a container used for domestic heating purposes for the storage of oil or liquid petroleum gas.

E1
a) Development is not permitted if total area of ground covered by the proposed building within the curtilage (excluding the ground area of the original house) would exceed 50% of the total area of the curtilage.

The proposed outbuilding covers less than 50% of the surrounding land.

b) Any part of the building would be situated on land forward of a wall the principle elevation of the original dwelling.

The proposed outbuilding is set in line with, therefore not in front of, the original principle elevation.

c) The building would have more than 1 storey.

The proposed building is single storey.

d) The height of the building would exceed (i) 2.5m in the case of a building is within 2m of the boundary.

The height of the proposed building is below 2.5m

e) The height of the eaves would exceed 2.5m.

The proposed eaves height is below 2.5m.

f) The building would be situated within the curtilage of a listed building.

35 Kentish Lane is not listed

g) includes a balcony or veranda

No balcony or veranda included

h) relates to domestic or microwave antenna

No antenna included

i) capacity of a container would exceed 3500 ltr.

Not a container

E2
Development is not permitted if any and within the curtilage of the dwelling house is within:

- a) a World Heritage Site
- b) A National Park
- c) An area of outstanding natural beauty
- d) OR the Broads

None of these apply.


E3
Restricts buildings on Article 1(5) land

This does not apply.

with reference to E1 (d)
The technical guidance, 'General Issues', confirms the height of a proposed building should be measured from ground level immediately adjacent to the proposed building. Where the ground is not level then ground level is the highest part of the surface of ground level next to the proposed building.

The height of the proposed outbuilding to 35 Kentish Lane is measured from the adjacent highest ground level to the rear.

Conclusion
There is no restriction to proximity to other buildings but it should not be physically attached otherwise it would have to comply with the criteria within Class A. This proposed outbuilding is not attached. Therefore this proposed outbuilding is regarded as Permitted Development and can be built without the need for Planning Permission.



Basic Section



Revision _____ Date _____

PNA

2 The Coach House, Comeybury Farm
Ermine Street, Buntingford, Herts, SG9 9RS
01763 271292 / 01707 276595
email : info@pna.eclipse.co.uk

Job Title
35 Kentish Lane
Brookmans Park
Hatfield Herts

Drawing Title
PROPOSED OUTBUILDING
Proposed Elevations & Section
Permitted Development

Date July 2016 Scale 1:100 @ A2

Job No 774 Drawing No PD/02

Copyright (c)