



Comp Type: MLZ015  
HP: 2  
Noise: 34  
Duty: -5 3600, -10 2950, -15 2370  
KG: 73  
Supply: 400v-3ph-50hz  
FLA: 6.5  
H: 844mm W:1025mm D:430mm  
Mounting holes: A:580mm B:397  
Valve size: Suction 3/4 Liquid: 3/8  
Low noise quality condensing units  
Quick Install range 2-6 PH  
Scroll compressor (single or three phase)  
3 phase monitoring device  
Fault indicator light  
Compressor jacket  
Panasonic condenser fan motor  
Danfoss dual pressure switch  
Danfoss liquid sight glass  
Danfoss filter drier  
Liquid receiver  
Low side gauge  
High side gauge  
Acoustic case lining  
Low side service valve  
High side service valve  
Panasonic fan speed regulator  
Supco adjustable time delay  
ABB Isolator switch  
ABB Contactor  
ABB Overload protector  
ABB MCB