



200mm deep white painted preservative treated timber barge boards

slate roofing to match lower pitched roofs

24mm thick sealed double glazed window units in Pilkington low E glass with argon gas infill set in 120mm x 80mm white painted preservative treated timber frames with 18mm rebates to take glazing

pair white painted preservative treated timber top hung side lights with 80mm x 70mm sills and rails and with 24mm sealed double glazed units in Pilkington low E glass with argon gas infill set in 18mm rebates

120mm x 100mm white painted preservative treated timber frames to door and side lights with 18mm rebates both sides & 180mm x 100mm hardwood timber threshold

80mm black rain water down pipes with deep flow gutters

multi red facing brick to match existing house


24mm thick sealed double glazed window units in Pilkington low E glass with argon gas infill set in 120mm x 80mm white painted preservative treated timber frames with 18mm rebates to take glazing

pair white painted 600mm wide rebated timber doors with 100mm x 70mm sills and top rail & 200mm x 70mm bottom rail and with 24mm sealed double glazed units in Pilkington low E glass with argon gas infill set in 18mm rebates

damp proof course set 150mm above external ground levels

ADDITIONAL
AMENDMENT
20 FEB 2008
NO. 56/2007/1345/LB

© Copyright Roger Carter ARIBA DipArch(Hons)

ROGER CARTER ARCHITECTS	
Chartered Architects 47, The Ryde Hatfield Hertfordshire tel: 01707 258955/262035	
	
18 FORE STREET	
OLD HATFIELD HERTS PROPOSED EXTENSIONS REAR ELEVATION TO LIVING ROOM	
Date: February 2008	Drawing No:
Scale: 1:20	947/06

18 FORE STREET
REAR ELEVATION TO LIVING ROOM