



PLANNING DEPARTMENT
OFFICE COPY
09 JAN 2002
NO: 86 02/59/19

WELWYN HATFIELD COUNCIL
TOWN & COUNTRY PLANNING ACT 1990
PLAN REFERRED TO IN
CONSENT / [REDACTED]
DATED: 18 FEB 2002

SPECIFICATION	
FLAT ROOF 12.5mm layer of stone chippings bedded in bitumen compound, 3 layers of bitumen felt to B.S. 747 Part 2: 1970 top layer to be high performance felt laid and built up in accordance with CP 144 Part 3: 1970, 100mm x 100mm SC4 grade s.w. joists @ 400mm c/c.	
COLD ROOF - 19mm plywood decking fixed to 100mm x 100mm x 38mm counter battens @ 400mm c/c. 150mm fibreglass insulation 500g polythene vapour barrier 12.5mm plasterboard and skim. 25mm continuous vent gap with fly screen to soffits.	
WARM ROOF - 75mm Celig Purdeck combined insulation and decking fixed to 100mm x 100mm x 38mm counter battens @ 400mm c/c. 150mm fibreglass insulation 500g polythene vapour barrier 12.5mm plasterboard and skim. 25mm continuous vent gap with fly screen to soffits.	
WALLS Waterproof rendering to B.S. 5262:1976 on 100mm celcon blockwork. Facing brick and bond to match existing 50mm cavity filled with dryform insulation batts. 100mm celcon block inner skin with 12mm plaster. Wall ties to B.S. 1243 staggered 900mm horizontally and 450mm vertically doubled at openings. Tooth in new walls and maintain cavities. Vertical gaps to all reveals. Head horizontal dpc min. 150mm above ground level and 100mm min. abs. Weak concrete fill to ground level. Walls parallel to timber restrained by 30mm x 5mm galv. m.s. anchor straps with noggin @ max. 2000mm c/c. engaging 3 no. joists/rafters.	
FOUNDATIONS AND SLAB 450mm wide 1:3:6 mass concrete foundations min. 500mm below ground level and to 600mm min. below any tree root activity and to invert level of adjacent drains, if deeper, foundations to comply with N.H.B.C. Practice Note 4.2. 75mm 1:3 cement/sand screed on 3 coats of synthaprupe dpm continuous with dpc on 125mm concrete on 38mm high density styrofoam floor insulation on 1200g polythene membrane on sand binding on 150mm well consolidated hardcore.	
DRAINAGE Expose any existing drains under new building and encase in 150mm concrete. New drains to be 110mm dia. upvc Osma drain to min. 1:40 falls bedded and surrounded in 100mm pea shingle. Provide r.c. inlets over any drain passing through walls or foundations and 75mm capping to drains with less than 600mm cover. New manholes to be 450mm dia. polypropylene Osma inspection chambers. Any inspection chambers or gullies within building to have bolted and sealed covers. Soffits where used when s.w. not available to be min. 500mm from any building. All drainage to be carried out to B.S. 8301:1995.	
DRAINAGE ABOVE GROUND 110mm dia. upvc soil and vent pipes to terminate min. 900mm above any windows and fitted with durable guard. 110mm dia. upvc soil pipe to wet 75mm deep soil traps 40mm dia. upvc waste to sinks, baths, basins and showers. Wastes greater than 3000mm long to have min. 75mm dia.	
FIRE PROTECTION Beams encased in two layers of 12.5mm gypsum plasterboard to break joint with 1.6mm wire bending @ 100mm pitch with 7mm gypsum plaster skim. * denotes half hour self closing fire door with 25mm door stops and 100mm non-combustible threshold to garage.	
SUB FLOOR VENTILATION Any air brick covered by new work ducted by 110mm dia. pipe under new floor to new 75 x 215mm air brick.	
DORMER CHEEKS Plain Hing / Pressure impregnated boarding on 38 x 25mm pressure impregnated battens on breather felt on 9mm sheathing plywood on 100 x 50mm studwork off doubled rafters. 100mm expanded polystyrene insulation between studs 500g polythene vapour barrier 12.5mm plasterboard and skim. Code 4 lead flashings and soakers to junctions to roof.	
FIREPLACES AND FLUES 125mm thick superimposed hearth to extend 150mm to sides and 500mm in front of jambs. Provide fixing points for fireguard. 200mm dia. clay flue liners to B.S. 1191. All timber trimmed min. 200mm away from flue and 50mm away from casing to flue. Code 4 lead back outlet, horizontal dpc flashings and soakers to junction of chimney with roof. 215 x 215mm air brick for combustion. Gas fired balanced flue terminals to be sited min. 300mm from any opening and fitted with durable wired guard.	
WINDOWS AND VENTILATION Double glazed windows and patio doors. All new glazing to comply with B.S. 6206:1981. Windows to provide 5% openings to habitable rooms. Min. 10,000mm ² ventilated heads to patio doors and 6000mm ² trickle vents to windows. Internal toilet accommodation vented by extractor fans ducted to external air. Fan wired to light switch and to run for 20 minutes after light switched off. Bathroom/shower rooms to have mechanical extract fan to clear 15 litres per second. Kitchen to have cooker hood extract fan to clear 30 litres per second.	
PITCHED ROOF AND CEILING Tiling and pitch to match existing on 38 x 25mm pressure impregnated battens on untearable roofing felt. Structure as shown on section. 200mm fibreglass insulation. 500g polythene vapour barrier. 12.5mm plasterboard and skim. Continuous dpc ventilators to be sloping insulation ceiling 12.5mm continuous vent strip to soffit and cross ventilated in accordance with B.S. 5250:1998.	
UPPER FLOORS 20mm flooring grade 1 & g chipboard type 11/111 to B.S. 5669 220 mm x 50mm SC4 grade s.w. joists @ 400mm c/c. 38mm x 38mm herringbone strutting 12.5mm plasterboard and skim to ceiling.	
LINTELS Cathic CN7 to openings up to 1800mm CN8 to wider openings. Min. 150mm end bearings.	
INTERNAL STUD PARTITIONS 100 x 50mm s.w. stud framing built off 100 x 75mm sole plates. Studs spaced @ 450mm c/c horizontally and 900mm vertically and fibreglass infill 12.5mm plasterboard and skim both sides. First floor joists doubled up and bolted together under stud partitions.	
STAIRS min. rise and min. going: 25mm nosings. Total rise of min. 190mm. Min. width 600mm. Min. 200mm bedroom vertically above pitch line. Handrail to be 900mm high above pitch line and on landings. Max gap to spindles 99mm.	
GENERAL All work to be carried out in accordance with the building regulations 1991 and current B.S. Codes of Practice. Adequacy of existing walls, lintels and foundations to be checked on site prior to loading. All dimensions must be checked on site and not scaled from this drawing. Materials and workmanship are to be to the satisfaction of the client matching existing where possible. All new electrical fittings, radiator positions etc. are to be agreed on site with client. The builder is to remove all debris as it accumulates and on completion leave the site tidy to the clients satisfaction.	
JOB TITLE COVERACK THE RIDGEWAY CUFFLEY HERTS	
DRAWING TITLE PROPOSED EXTENSIONS AND ALTERATIONS	
CLIENT MR & MRS J. PERKINS	
SCALE 1:50	
DATE NOVEMBER 2000	
DRG. No. 02A	
AMENOMENTS A Client / Planning B C	
Neil Anderson Planning and Building Design Services	
1a WOODLAND WAY OAKLANDS WELWYN HERTS. AL6 0RZ TEL/FAX: (01438) 717854	