TREE SCHEDULE

No.	DIAMETER	SPREAD	HEIGHT	SPECIES
1	0.2	4	3	HOLLY
2	0.3	6	8	LOCUST
3	0.225	6	8	LOCUST
4	0.2	6	8	LOCUST
5	0.2	6	8	LOCUST
6	0.2	6	8	LOCUST
7	0.2	6	8	LOCUST
8	0.15	4	8	LOCUST
9	0.8	8	10	OAK
10	0.2	6	8	LOCUST
11	0.4	6	6	FIR
12	1.1	16	14	OAK
13	0.3	6	8	SYCAMORE
14	0.3	6	8	SYCAMORE
15	0.8	10	14	ASH
16	0.2	6	8	SYCAMORE
17	0.4	6	8	SYCAMORE
18	0.2	6	8	SYCAMORE
19	0.1	4	2	RHODODENDRON
20	0.3	4	2	RHODODENDRON
21	0.3	4	2	RHODODENDRON
22	0.2	6	6	S/BIRCH
23	0.45	8	8	S/BIRCH
24	0.45	8	8	S/BIRCH
25	1.0	8	6	WILLOW
26	0.2	6	6	WILLOW
27	0.1	4	5	S/BIRCH
28	0.1	4	5	S/BIRCH
29	0.1	4	5	S/BIRCH
30	0.1	4	5	S/BIRCH
31	0.1	4	5	S/BIRCH
32	0.1	4	5	S/BIRCH
33	0.4	6	6	S/BIRCH
34	0.1	4	6	S/BIRCH
35	0.1	4	6	S/BIRCH
36	0.1	4	6	S/BIRCH
37	0.2	6	6	HORNBEAM
38	0.4	6	6	HORNBEAM
39	0.4	6	6	HORNBEAM
40	0.4	6	6	HORNBEAM
41	0.1	3	2	ELDER
42	0.2	6	6	SYCAMORE
43	0.8	10	12	SYCAMORE
44	0.1	3	3	ELDER
45	0.15	4	4	HAZEL
46	0.5	6	6	SYCAMORE
47	0.4	6	10	CHERRY
48	0.1 MB	6	6	BAY
49	0.8	8	10	SYCAMORE
50	0.8	8	10	SYCAMORE
51	0.8	8	10	PINE
52	0.2	3	4	S/BIRCH
53	0.1	3	4	OAK
54	0.8	10	14	PINE
55	0.8	10	10	OAK
56	0.4	6	6	HOLLY
57	0.5	10	10	OAK
58	0.4	6	8	CYPRESS
59	0.4	6	8	CYPRESS
60	0.2	6	8	CYPRESS
61	0.45	6	8	CYPRESS
62	0.3	6	8	CYPRESS
63	0.4	8	8	OAK
64	0.8	8	8	CYPRESS
65	0.8	8	8	CYPRESS
66	0.8	6	5	YEW
67	0.8	8	10	S/BIRCH
68	0.5	8	8	SYCAMORE
69	0.3	6	5	YEW
70	0.25	6	5	CHERRY TO BE REMOVED
71	1.2	20	16	OAK
72	0.4	8	8	CHERRY
73	0.3	6	8	S/BIRCH
74	0.3	6	8	OAK
75	0.4	6	6	OAK
76	0.45	6	8	S/BIRCH
77	1.0	14	14	OAK
78	0.8	8	10	S/BIRCH
79	0.5	8	10	S/BIRCH
80	0.7	8	10	S/BIRCH
81	0.4	6	8	S/BIRCH
82	0.3	6	8	S/BIRCH
83	0.3	6	8	S/BIRCH
84	0.4	8	10	S/BIRCH
85	0.5	6	8	S/BIRCH
86	0.15	4	3	FRUIT
87	0.15	4	3	FRUIT
88	0.4	6	8	S/BIRCH
89	0.3	6	6	FRUIT
90	0.2	4	4	FRUIT
91	0.2	4	4	FRUIT
92	0.4	8	8	OAK
93	0.35	6	8	OAK
94	0.1 MB	6	6	HAWTHORN
95	1.0	16	16	OAK
96	0.3	6	6	HAWTHORN
97	0.3	6	6	HAWTHORN
98	0.5	6	4	HAWTHORN
99	0.5	6	4	HAWTHORN
100	0.2	4	4	HAWTHORN
101	0.5	6	4	HAWTHORN
102	0.2	4	4	HAWTHORN
103	0.2	4	4	HAWTHORN
104	0.5	4	4	HAWTHORN
105	0.3	6	10	SYCAMORE
106	0.8	10	12	SYCAMORE
107	0.3	8	10	SYCAMORE
108	0.5	4	4	HORNBEAM
109	1.2	20	20	OAK
110	0.8	8	10	OAK
111	0.5	8	10	S/BIRCH
112	0.1	4	2	UNKNOWN
113	0.8	10	12	S/BIRCH
114	0.2	8	8	HAWTHORN
115	0.2	4	3	HOLLY
116	0.4	4	4	MAPLE
117	0.1	4	6	UNKNOWN
118	1.0	20	20	OAK
119	0.15	4	4	HAWTHORN
120	0.4	8	8	HOLLY
121	0.1	3	2	ELDER
122	0.1	3	2	ELDER
123	1.0	20	20	OAK
124	0.1	2	2	ELDER
125	0.1	2	2	ELDER
126	0.5 MB	20	20	ASH
127	0.4	6	10	S/BIRCH
128	0.2	4	8	ROWAN
129	0.3	4	8	ROWAN
130	0.4	14	16	S/CHESTNUT
131	1.1	14	14	S/CHESTNUT
132	0.4	12	12	S/CHESTNUT
133	1.0	12	14	OAK
134	0.15	4	4	ROWAN
135	0.2	6	8	S/BIRCH
136	1.2	20	20	OAK
137	0.5	12	10	OAK
138	1.5	20	18	S/CHESTNUT
139	0.225	6	6	OAK
140	0.45	8	12	S/CHESTNUT
141	0.1	6	6	S/BIRCH
142	0.4	8	10	S/BIRCH
143	0.5	8	10	S/BIRCH
144	1.2	20	20	S/CHESTNUT
145	1.2	20	20	OAK
146	0.4	6	6	CYPRESS
147	1.0	12	14	OAK
148	0.4	6	10	CYPRESS
149	0.5	12	10	OAK
150	0.8	10	10	S/BIRCH
151	0.45	10	12	S/BIRCH
152	0.15	6	10	CYPRESS
153	0.4	6	10	CYPRESS
154	0.8	10	16	CEDAR
155	0.4	6	6	FIG
156	0.4	6	12	CYPRESS
157	0.3	6	4	YEW
158	0.15	4	6	CYPRESS
159	0.7	6	14	CYPRESS
160	0.1	3	3	YEW
161	0.1	3	3	YEW
162	0.2	4	12	CYPRESS
163	0.15	4	5	CYPRESS
164	0.2	6	14	CYPRESS
165	0.3	10	14	CYPRESS
166	0.3	6	5	PISSARD PLUM
167	0.4	6	10	CHERRY PLUM
168	0.3	6	10	HORNBEAM
169	0.15	4	4	JAP MAPLE
170	0.15	3	2	YEW
171	0.4	6	10	CYPRESS TO BE REMOVED
172	0.5	6	10	CYPRESS TO BE REMOVED
173	0.3	6	10	CYPRESS TO BE REMOVED
174	0.3	6	10	SYCAMORE TO BE REMOVED
175	0.8	12	16	OAK
176	0.3	6	6	WHCHESTNUT
177	0.6	6	12	CYPRESS
178	0.6	6	12	CYPRESS
179	0.225	4	10	CYPRESS
180	0.5	6	10	CYPRESS
181	0.5	6	10	CYPRESS
182	0.5	6	10	CYPRESS
183	0.5	6	12	CYPRESS
184	0.5	10	12	SYCAMORE
185	0.5	6	10	CYPRESS
186	0.6	12	14	OAK
186A	0.2	10	6	CYPRESS
187	0.1 MB	7	6	HAWTHORN
188	0.6	12	12	UNKNOWN
189	0.1 MB	3	3	HAWTHORN
190	0.3	8	12	S/BIRCH
191	0.1 MB	3	6	HAZEL
192	0.1 MB	3	6	HAZEL
193	0.1	6	10	OAK
194	0.3	6	10	OAK
195	0.15	6	10	OAK
196	0.1	6	6	OAK
197	0.15	6	12	OAK
198	0.1	6	6	OAK
199	0.2	6	10	OAK
200	0.1	4	8	OAK
201	0.2	6	10	OAK
202	0.1 MB	6	10	OAK
203	0.1	6	8	ROWAN
204	0.1	6	8	S/BIRCH
205	0.15	6	8	ROWAN
206	0.1	6	8	ROWAN
207	0.5	12	15	OAK
208	0.2	8	12	OAK
209	0.1 MB	6	6	S/CHESTNUT
210	0.1 MB	10	10	ROWAN
211	0.3	8	12	S/BIRCH
212	0.4	6	8	S/BIRCH
213	0.5	12	16	OAK
214	0.3	8	12	S/BIRCH
215	0.3	9	12	SYCAMORE
216	0.1	9	12	SYCAMORE
217	0.3 2B	8	12	SYCAMORE
218	0.15	9	12	SYCAMORE
219	0.1	8	10	SYCAMORE
220	0.2	8	12	SYCAMORE
221	0.2	9	12	SYCAMORE
222	0.1	6	8	WILLOW
223	0.1	5	8	S/BIRCH
224	0.2	6	10	CYPRESS

ABBREVIATIONS

AB	Air Brick	DH	Duct Height	FWF	Post & Rail Fence
BB	Bottom of Bottle Height	DW	Door Width	FWP	Post & Wire Fence
BB	Bristle Blocks	ECB	Electricity Control Box	R	Radius
BD	Back Drop	ELEC	Electricity	RAD	Radiator
BH	Bottle Height - Base Height	EP	Electricity Pole	RB	Rodding Eye
BL	Bed Level	FB	Flower Bed	RG	Rough Grassed
BP	Brick Pavers	FH	Fire Hydrant	RG	Road Sign
BRW	Brick Retaining Wall	FL	Floor Level	RSJ	Rolled Steel Joint
BS	Box Step	G	Gully	RWP	Rain Water Pipe
BTCB	Bottle Type Cascade	GD	Gas Drain	SC	Stop Cock
BTCB	BT Control Box	H	Height in Metres	SD	Stop Cock
BW	Brick Wall	HW	Window Head Height	SL	Soffit Level or Skylight
C	Concrete Fence	IC	Inspection Cover	SP	Soil Vent Pipe
C	Window C/O Height	IC	Inspection Cover	SPS	Stone Paving Slabs
CB	Control Box	IL	Invert Level	SW	Stone Wall
CBF	Close Boarded Fence	IWF	Ironmongers Fence	T	Top Heights
CBM	Concrete Block Wall	IWF	Ironmongers Fence	T	Top Heights
CCB	Cable TV Control Box	KO	Kerb Outlet	TL	Traffic Light
CCP	Corrugated Iron Fence	L	Light	TP	Telephone Pole
CL	Cover Level	LP	Lamp Post	TPS	Tactile Paving Slabs
CLF	Chain Link Fence	MH	Manhole	TPS	Tactile Paving Slabs
CLSF	Chain Link Security Fence	MKR	Marker	U	Urinal
CPF	Concrete Panel Fence	OF	Over Flow Pipe	VP	Vent Pipe
CPS	Concrete Post Fence	P/H	Pothole	W	Window
CR	Kerb Crown Height	P	Post	WL	Water Level
CRW	Concrete Retaining Wall	PALF	Palisade Fence	WM	Water Meter
CTV	Cable Television	PC	Pedestal Crane	WP	Weather Pipe
CTV	Cable Television	PCC	Trial Pit	WPF	Wooden Panel Fence
CW	Concrete Wall	PL	Pavement Light	WV	Water Valve
D	Diameter or Drain	PM	Parking Meter	Ø	Diameter

Banks
Kerbs
Drop Kerbs
Overhead Details
Change in Elevation
Fences
Underground Cables
Change in Surface
Edge of Vegetation
Floor to Ceiling Height
False Ceiling Height
Gate
Survey Station
Foul Water Sewer
Surface Water Sewer
Combined Sewer

LEVEL NOTE.
ALL CO-ORDINATES RELATE TO THE ORDNANCE SURVEY
ALL CO-ORDINATES RELATE TO THE ORDNANCE SURVEY

COORDINATE SCHEDULE

STN	EASTING	NORTHING	LEVEL
01	529254.68	264862.69	127.56
02	529257.60	264851.94	127.49
03	529260.40	264841.24	127.42
04	529263.40	264830.50	127.34
05	529266.70	264819.30	127.27
06	529269.80	264808.60	127.19
07	529272.90	264797.90	127.12
08	529276.00	264787.20	127.04
09	529279.00	264776.50	126.97
10	529282.00	264765.80	126.90
11	529285.00	264755.10	126.82
12	529288.00	264744.40	126.75
13	529291.00	264733.70	126.68
14	529294.00	264723.00	126.60
15	529297.00	264712.30	126.53
16	529300.00	264701.60	126.46
17	529303.00	264690.90	126.38
18	529306.00	264680.20	126.31
19	529309.00	264669.50	126.24
20	529312.00	264658.80	126.16
21	529315.00	264648.10	126.09
22	529318.00	264637.40	126.02
23	529321.00	264626.70	125.94
24	529324.00	264616.00	125.87
25	529327.00	264605.30	125.80
26	529330.00	264594.60	125.72
27	529333.00	264583.90	125.65
28	529336.00	264573.20	125.58
29	529339.00	264562.50	125.50
30	529342.00	264551.80	125.43
31	529345.00	264541.10	125.36
32	529348.00	264530.40	125.28
33	529351.00	264519.70	125.21
34	529354.00	264509.00	125.14
35	529357.00	264498.30	125.06
36	529360.00	264487.60	124.99
37	529363.00	264476.90	124.92
38	529366.00	264466.20	124.84
39	529369.00	264455.50	124.77
40	529372.00	264444.80	124.70
41	529375.00	264434.10	124.62
42	529378.00	264423.40	124.55
43	529381.00	264412.70	124.48
44	529384.00	264402.00	124.40
45	529387.00	264391.30	124.33
46	529390.00	264380.60	124.26
47	529393.00	264369.90	124.18
48	529396.00	264359.20	124.11
49	529399.00	264348.50	124.04
50	529402.00	264337.80	123.96
51	529405.00	264327.10	123.89
52	529408.00	264316.40	123.82
53	529411.00	264305.70	123.74
54	529414.00	264295.00	123.67
55	529417.00	264284.30	123.60
56	529420.00	264273.60	123.52
57	529423.00	264262.90	123.45
58	529426.00	264252.20	123.38
59	529429.00	264241.50	123.30
60	529432.00	264230.80	123.23
61	529435.00	264220.10	123.16
62	529438.00	264209.40	123.08
63	529441.00	264198.70	123.01
64	529444.00	264188.00	122.94
65	529447.00	264177.30	122.86
66	529450.00	264166.60	122.79
67	529453.00	264155.90	122.72
68	529456.00	264145.20	122.64
69	529459.00	264134.50	122.57
70	529462.00	264123.80	122.50
71	529465.00	264113.10	122.42
72	529468.00	264102.40	122.35
73	529471.00	264091.70	122.28
74	529474.00	264081.00	122.20
75	529477.00	264070.30	122.13
76	529480.00	264059.60	122.06
77	529483.00	264048.90	121.98
78	529486.00	264038.20	121.91
79	529489.00	264027.50	121.84
80	529492.00	264016.80	121.76
81	529495.00	264006.10	121.69
82	529498.00	263995.40	121.62
83	529501.00	263984.70	121.54
84	529504.00	263974.00	121.47
85	529507.00	263963.30	121.40
86	529510.00	263952.60	121.32
87	529513.00	263941.90	121.25
88	529516.00	263931.20	121.18
89	529519.00	263920.50	121.10
90	529522.00	263909.80	121.03
91	529525.00	263899.10	120.96
92	529528.00	263888.40	120.89
93	529531.00	263877.70	120.81
94	529534.00	263867.00	120.74
95	529537.00	263856.30	120.67
96	529540.00	263845.60	120.59
97	529543.00	263834.90	120.52
98	529546.00	263824.20	120.45
99	529549.00	263813.50	120.38
100	529552.00	263802.80	120.30
101	529555.00	263792.10	120.23
102	529558.00	263781.40	120.16
103	529561.00	263770.70	120.08
104	529564.00	263760.00	120.01
105	529567.00	263749.30	119.94
106	529570.00	263738.60	119.86
107	529573.00	263727.90	119.79
108	529576.00	263717.20	119.72
109	529579.00	263706.50	119.64
110	529582.00	263695.80	119.57
111	529585.00	263685.10	119.50
112	529588.00	263674.40	119.42
113	529591.00	263663.70	119.35
114	529594.00	263653.00	119.28

COPYRIGHT: The contents of this drawing may not be reproduced in part or in whole without the written consent of Building Design Consultants

PROJECT: Proposed replacement of stable block with garage
DRAWING NUMBER: 11015/12
DRAWING: Site plan as existing, with features and levels
CLIENT: Mr and Mrs M. Vignali
SITE: 45 Kenrish Lane, Brookmans Park, Hatfield, AL9 6NG
DATE: February 2012
SCALES: 1:200 @ A0

Building Design Consultants
ARCHITECTURAL DESIGNERS
STRUCTURAL ENGINEERS
BUILDING SURVEYORS
PLANNING CONSULTANTS
BUILDING CONSULTANTS
47 Deer Park Way, Waltham Abbey, Essex EN9 3YN
www.plansanddesigns.uk
Tel: 01992 768866 Fax: 01992 768877

Amendments:

THIS WORK MAY BE AFFECTED BY THE PROVISIONS OF THE PARTY WALL etc. ACT 1996
THE CONTRACTOR MAY BE RESPONSIBLE FOR NOTIFYING HSE UNDER CDM REGULATIONS 1994
IF THE PROJECT IS COMMERCIAL OR INDUSTRIAL, A PLANNING SUPERVISOR SHOULD BE APPOINTED.