



existing wall taken down

existing wall, floor and joists removed

glass panel

1100

new pre-finished overlaid floor

existing floor and joists

wheelchair platform lift by specialist supplier

1535

75mm sand:cement screed on separating layer on 100mm Kooltherm K103 rigid insulation on 100mm concrete slab on DPM on 25mm sand blinding on hardcore

100mm dense block dwarf wall on existing slab

existing floor

SECTION C - C

| rev | description | date |
|--|-------------|---------|
| STEPHEN J VINEY architect 178 Botley Road, Chesham, Bucks, HP5 1XR 01494 791949 M 07788 628 820 steve_viney@hotmail.com | | |
| client | | |
| Gascoyne Holdings Ltd Hatfield House | | |
| project | | |
| St Ethelreda's Church Hall | | |
| drawing | | |
| Details Lift | | |
| date | scale | dwg no |
| Sept 17 | 1:10 | HHCH/15 |
| | | rev |