



- Existing Trees - Retained
- Existing Trees - Route Protection Area
- Existing Trees - Removed
- Existing Vegetation - Retained  
To be managed and infilled where required
- Existing Grass - Retained
- Proposed Conifer Tree
- Proposed Single-Stem Tree
- Proposed Multi-Stem Tree
- Proposed Specimen
- Proposed Hedge  
Carpinus betulus  
3L plants @ 5no./linear meter
- Proposed Ornamental Planting
  - Mix 1 - Low Edge Mix  
2L plants planted @6/m<sup>2</sup>  
Liriope 'Big Blue' 10%  
Luzula sylvatica 10%  
Prunus laurocerasus 'Low n' Green' 25%  
Sesleria autumnalis 35%  
Sedum 'Autumn Joy' 20%
  - Mix 2 - Structure shrubs and accent mix  
2L plants planted @4/m<sup>2</sup>  
Anemranthe lessoniana 15%  
Calamagrostis 'Karl Foerster' 10%  
Cornus 'Mid Winter Fire' 10%  
Cornus alba 'Sibirica' 10%  
Hebe 'Margaret' 25%  
Sarcococca hookeriana 'Winter Gem' 30%

- Proposed Native Planting  
3L plants planted @ 3/m<sup>2</sup> in groups of 5-7  
Each plant to be fitted with a rabbit guard  
Cornus sanguinea 20%  
Corylus avellana 20%  
Crataegus monogyna 20%  
Euonymus europaeus 10%  
Ilex aquifolium 10%  
Lonicera periclymenum 10%  
Prunus spinosa 5%  
Rosa canina 5%
- Proposed Amenity Grass
- Proposed Green Roof  
Sedum Carpet  
e.g. Nature Mat by Blackdown Green Roofs,  
containing a mix of hardy sedums both  
native and non native.

Revision	Description	Drawn by	Checked by	Date
P2	Base updated with latest landscape plan	MR	LP	02.03.23

Macgregor • Smith  
Landscape Architecture

project	Hatfield Business Park Plot 5610	drawn by	MR
status	Planning	checked by	LP
title	Planting Plan	date	29.11.22
Xref	1221-01 Mastermodel	scale	@a1
drawing No	drawing no	revision	P2

This drawing is protected by copyright. Contractors must check all dimensions on site. Only figure dimensions are to be worked from. Discrepancies must be reported to architect before proceeding.  
Christopher House, 11-12 High Street, Bath, BA1 5AG. Tel: 01225 464 690. info@macgregorsmith.co.uk