




front elevation




rear elevation



side elevation



side elevation



External walls: Cavity brickwork / blockwork:  
100mm facing bricks to match existing - 100mm cavity filled with 100mm rigid fibre-glass insulation and 100mm Thermacore blocks with 13mm plaster internally.

Provide stainless steel twisted cavity wall ties at 750mm horizontal centres and 450mm staggered vertical centres. Ties to be doubled up at corners and reveals.

Provide insulated cavity closers to all new reveals.

Note - External walls to achieve a minimum U' value of 0.28w/m<sup>2</sup>K.

Note- Provide insulated cavity closers to all new reveals.

Note - Please refer to Structural Engineers design for beam and associated supports.

Note - All new materials to match existing.


Note - Provide a self contained, mains operated, interlinked optical smoke detector system with battery back-up in accordance with BS 5839 or 5446 should be provided on each floor landing (ground floor and first floor landing levels) (B1). While giving due consideration to providing an additional smoke detector on the opposite landing so that each wing of the property is fully protected.

Note - If gas or electric meters are located under the stair cupboards than the understair cupboards and cupboard doors should be lined with fire line plaster board.

Note - Electrical installation to be carried out by a member of an Electrical Competent Person Scheme (ECPs) who on completion of the work must register the installation with their ECPs in order that a completion certificate can be issued.


Note - All boiler installations to be carried out and certified by a member or a class of persons approved by the HSE; for the time being this means they must be registered with Gas Safe, the Council of Registered Gas Installers.

Note - The SEDRUK 2009 seasonal efficiency rating of any proposed boiler should not be less than 85%.




No part of the construction to encroach the boundary.

Bond new structure to existing using s/s profiles by cement or similar approved.



ground floor plan



scale bar 1:50

63mm rwp to connect to existing surface water drain or taken via 100mm heepsleeve drains laid on 150mm pea shingle to a soakaway located 5m away from any building.  
Note - Soakaway to be designed 1m<sup>3</sup> for every 16m<sup>2</sup> of roof area drained.

Remove walls as shown dotted and provide new steel beams over to engineer's detail, and cut back brickwork as required.

All new wastes to kitchen area be 40mm fitted with 75mm deep seal traps and cleaning eyes provided at changes of direction. 100mm h.i. gully connected to existing manhole.

Form all new timber stud partitions as shown on the drawing constructed in 100x50mm softwood timber at 400mm centres with 12.5mm plaster board and skim coat of plaster to both sides and infill with 100mm rockwool insulation. All new studs to be built of double joists bolted together with M12 Bolts at 600mm centres.

Note - New h.i. gully taking sink waste and connect to new drain and existing drain run.

Note - Provide mechanical ventilation ducted to fresh air to utility with an extract rate of 30 litres/sec operated by means of the light switch with a minimum of 15 minutes overrun.

All new wastes to utility be 40mm fitted with 75mm deep seal traps and cleaning eyes provided at changes of direction and connected to existing s.v.p or new 100mm s.v.p.

Note - Heated wholesome water or heated softened water to proposed wash hand basins and shower to be installed so as to resist the effects of temperature and pressure that may occur either in normal use or in the event of such malfunctions as may reasonably be anticipated, and must be adequately supported.

New 100mm drains laid to a fall of 1:40 and surrounded in 150mm pea shingle and connected to existing drain run.

Note - Any existing or proposed drains found under the proposed extension are to be surrounded in 150mm pea shingle and bridged with concrete and reinforced concrete lintels.

Notes

This drawing is the Copyright of Blyth developments, and may not be reproduced or copied, in whole or in part, without express permission.

Figured dimensions shall be used in preference to scaled dimensions. All dimensions shall be checked on site before commencing works.

All work shall comply with the latest Building Regulations and be to the satisfaction of the Local Authority.

Workmanship and methods of construction shall be at least to the standards prescribed by the relevant Codes of Practice.

Materials shall be suitable for the purpose for which they are used and the quality shall not be lower than that defined in the relevant British or Continental Standard so designated.

General Specifications

1. All drainage shown on this drawing is assumed only and it is the contractors responsibility to check exact depths and locations prior to the commencement of the works. or proposed drains found under the proposed extension are to be surrounded in 150mm pea shingle and reinforced concrete lintels are to be provided in the walls above the drain run.
2. Existing sub-floor ventilation is to be maintained (if necessary) by providing 100mm dia pvc ducts extending from the existing air bricks to not less than 150mm.
3. Existing sub-floor ventilation is to be maintained (if necessary) by providing 100mm dia pvc ducts extending from the existing air bricks to not less than 150mm.
4. All glazing is to be double glazed and to be to BS6206 and any glazing within 800mm of the floor level is to be completed or laminated in accordance with Part K.

5. All new habitable rooms are to be provided with permanent ventilation of 600mm<sup>3</sup> and this is to be achieved by providing either trickle vents in the window or by providing mechanical ventilation of 600mm<sup>3</sup> and all linings are to have a minimum and bearing of 150mm.
6. Provide vertical and horizontal dips at all reveals, and all linings are to have a minimum and bearing of 150mm.
7. All steel beams are to be covered in 2 layers of 12.5mm plaster board and skim coat of plaster to achieve a fire rating of 12 hour.
8. All steel beams are to be covered in 2 layers of 12.5mm plaster board and skim coat of plaster to achieve a fire rating of 12 hour.
9. All glazing is to be low E glass with 100mm air gaps between panes.
10. Provide one hour energy light fitting in new extension.
11. All electrical work required to meet the requirements of Part P (Electrical Safety) must be designed, installed, inspected and tested by a person competent to do so, prior to completion. All work should be to BS 7671 and Part P has been taken into account and all work should be to BS 7671 and Part P. A completion certificate to be issued for the work by a person competent to do so.

Note - All baths / showers to be fitted with thermostatic valves so that the hot supply does not exceed 48 deg C.

Note - Provide thermostatic radiator valves to new proposed radiators.

Revisions	To Clients Requirements.
A	28.02.22

**Proposed plans and elevations.**  
37 Walker Grove  
Hardfield Hertfordshire AL10 9PL.  
Mr. C. Huang & Mrs. Y. Li.

**blyth developments**  
155 Briar Road  
Watford  
Hertfordshire  
WD25 0HL.  
T: 020 8428 6868

Scale 1:50 1:100 @ A1  
Date February 2022  
Drawn By D. J. BLYTH.  
Drawing No: **BD/22/09/3A**