TREE SCHEDULE

No.	DIAMETER	SPREAD	HEIGHT	SPECIES
1	0.2	4	3	HOLLY
2	0.3	6	8	LOCUST
3	0.25	6	8	LOCUST
4	0.2	6	8	LOCUST
5	0.2	6	8	LOCUST
6	0.2	6	8	LOCUST
7	0.2	6	8	LOCUST
8	0.15	4	8	LOCUST
9	0.6	8	10	LOCUST
10	0.2	6	8	LOCUST
11	0.4	6	8	FIR
12	1.1	16	14	OAK
13	0.3	6	8	SYCAMORE
14	0.3	6	8	SYCAMORE
15	0.8	10	14	ASH
16	0.2	6	8	SYCAMORE
17	0.4	6	8	SYCAMORE
18	0.2	6	8	SYCAMORE
19	0.1	4	2	RHODODENDRON
20	0.3	4	2	RHODODENDRON
21	0.3	4	2	RHODODENDRON
22	0.2	6	6	S/BIRCH
23	0.45	8	8	S/BIRCH
24	0.45	8	8	S/BIRCH
25	1.0	8	6	WILLOW
26	0.2	6	8	WILLOW
27	0.1	4	5	S/BIRCH
28	0.1	4	5	S/BIRCH
29	0.1	4	5	S/BIRCH
30	0.1	4	5	S/BIRCH
31	0.1	4	5	S/BIRCH
32	0.1	4	5	S/BIRCH
33	0.4	6	6	S/BIRCH
34	0.1	4	6	S/BIRCH
35	0.1	4	6	S/BIRCH
36	0.1	4	6	S/BIRCH
37	0.2	6	6	HORNBEAM
38	0.4	6	6	HORNBEAM
39	0.4	6	6	HORNBEAM
40	0.4	6	6	HORNBEAM
41	0.1	3	2	ELDER
42	0.2	6	6	SYCAMORE
43	0.6	10	12	SYCAMORE
44	0.1	3	3	ELDER
45	0.15	4	4	HAZEL
46	0.5	6	6	SYCAMORE
47	0.4	6	10	CHERRY
48	0.1 MB	6	6	BAY
49	0.6	8	10	SYCAMORE
50	0.6	8	10	SYCAMORE
51	0.6	6	10	PINE
52	0.2	3	4	S/BIRCH
53	0.1	3	4	OAK
54	0.8	10	14	PINE
55	0.6	10	10	OAK
56	0.4	6	6	HOLLY
57	0.5	10	10	OAK
58	0.4	6	8	CYPRESS
59	0.4	6	8	CYPRESS
60	0.2	6	8	CYPRESS
61	0.45	6	8	CYPRESS
62	0.3	6	8	CYPRESS
63	0.4	8	8	OAK
64	0.8	8	8	CYPRESS
65	0.8	8	8	CYPRESS
66	0.6	6	5	YEW
67	0.8	8	10	S/BIRCH
68	0.5	8	8	SYCAMORE
69	0.3	6	5	YEW
71	1.2	20	16	OAK
72	0.4	8	8	CHERRY
73	0.3	6	8	S/BIRCH
74	0.3	6	8	OAK
75	0.4	6	6	OAK
76	0.45	6	8	S/BIRCH
77	1.0	14	14	OAK
78	0.6	8	10	S/BIRCH
79	0.5	8	10	S/BIRCH
80	0.7	8	10	S/BIRCH
81	0.4	6	8	S/BIRCH
82	0.3	6	8	S/BIRCH
83	0.3	6	8	S/BIRCH
84	0.4	8	10	S/BIRCH
85	0.5	8	6	S/BIRCH
86	0.15	4	3	FRUIT
87	0.15	4	3	FRUIT
88	0.4	6	8	S/BIRCH
89	0.3	6	6	FRUIT
90	0.2	4	4	FRUIT
91	0.2	4	4	FRUIT
92	0.4	8	8	OAK
93	0.35	6	8	OAK
94	0.1 MB	8	8	HAWTHORN
95	1.0	16	16	OAK
96	0.3	6	6	HAWTHORN
97	0.3	6	6	HAWTHORN
98	0.3	6	4	HAWTHORN
99	0.5	6	4	HAWTHORN
100	0.2	4	4	HAWTHORN
101	0.5	6	4	HAWTHORN
102	0.2	4	4	HAWTHORN
103	0.2	4	4	HAWTHORN
104	0.5	4	4	HAWTHORN
105	0.3	6	10	SYCAMORE
106	0.6	10	12	SYCAMORE
107	0.3	8	10	SYCAMORE
108	0.5	4	4	HORNBEAM
109	1.2	20	20	OAK
110	0.6	8	10	OAK
111	0.5	8	10	S/BIRCH
112	0.1	4	2	UNKNOWN
113	0.6	10	12	S/BIRCH
114	0.2	8	8	HAWTHORN
115	0.1	3	3	HORNBEAM
116	0.4	4	4	MAPLE
117	0.1	4	6	UNKNOWN
118	1.0	20	20	OAK
119	0.15	4	4	HAWTHORN
120	0.4	8	8	HOLLY
121	0.1	3	2	ELDER
122	0.1	3	2	ELDER
123	1.0	20	20	OAK
124	0.1	2	2	ELDER
125	0.1	2	2	ELDER
126	0.5 MB	20	20	ASH
127	0.4	6	10	S/BIRCH
128	0.2	4	8	ROWAN
129	0.3	4	8	ROWAN
130	0.9	14	16	S/CHESTNUT
131	1.1	14	14	S/CHESTNUT
132	0.9	12	12	S/CHESTNUT
133	1.0	12	14	OAK
134	0.15	4	4	ROWAN
135	0.2	6	8	S/BIRCH
136	1.2	20	20	OAK
137	0.5	12	10	OAK
138	1.5	20	18	S/CHESTNUT
139	0.25	6	6	OAK
140	0.45	8	12	S/CHESTNUT
141	0.1	6	6	S/BIRCH
142	0.9	8	10	S/BIRCH
143	0.5	8	10	S/BIRCH
144	1.2	20	20	S/CHESTNUT
145	1.2	20	20	OAK
146	0.4	6	6	CYPRESS
147	1.0	12	14	OAK
148	0.4	6	10	CYPRESS
149	0.5	12	10	OAK
150	0.6	10	10	S/BIRCH
151	0.45	10	12	S/BIRCH
152	0.15	6	10	CYPRESS
153	0.4	6	10	CYPRESS
154	0.6	10	16	CEDAR
155	0.4	6	6	FIG
156	0.4	6	12	CYPRESS
157	0.3	6	4	YEW
158	0.15	4	6	CYPRESS
159	0.7	6	14	CYPRESS
160	0.1	3	3	YEW
161	0.1	3	3	YEW
162	0.2	4	12	CYPRESS
163	0.15	4	5	CYPRESS
164	0.2	8	14	CYPRESS
165	0.5	10	14	CYPRESS
166	0.3	6	5	PISSARD PLUM
167	0.4	8	10	CHERRY PLUM
170	0.15	3	2	YEW
175	0.8	12	16	OAK
176	0.3	6	6	H/CHESTNUT
177	0.6	6	12	CYPRESS
178	0.6	6	12	CYPRESS
179	0.25	4	10	CYPRESS
180	0.5	6	10	CYPRESS
181	0.5	6	10	CYPRESS
182	0.5	6	12	CYPRESS
183	0.5	6	12	CYPRESS
184	0.5	10	12	SYCAMORE
185	0.5	6	10	CYPRESS
186	0.6	12	14	OAK
186A	0.2	10	6	CYPRESS
187	0.1 MB	7	8	HAWTHORN
188	0.6	12	12	UNKNOWN
189	0.1 MB	3	3	HAWTHORN
190	0.3	8	12	S/BIRCH
191	0.1 MB	3	6	HAZEL
192	0.1 MB	3	6	HAZEL
193	0.1	6	10	OAK
194	0.3	6	10	OAK
195	0.15	6	10	OAK
196	0.1	6	6	OAK
197	0.15	6	12	OAK
198	0.1	6	8	OAK
199	0.2	6	10	OAK
200	0.1	4	8	OAK
201	0.2	6	10	OAK
202	0.1 MB	6	10	OAK
203	0.1	6	8	ROWAN
204	0.1	6	8	S/BIRCH
205	0.15	6	8	ROWAN
206	0.1	6	8	ROWAN
207	0.5	12	15	OAK
208	0.2	8	12	OAK
209	0.1 MB	6	8	S/CHESTNUT
210	0.1 MB	10	10	ROWAN
211	0.3	8	12	S/BIRCH
212	0.4	6	8	S/BIRCH
213	0.5	12	16	OAK
214	0.3	8	12	S/BIRCH
215	0.3	9	12	SYCAMORE
216	0.1	9	12	SYCAMORE
217	0.3 2B	8	12	SYCAMORE
218	0.15	9	12	SYCAMORE
219	0.1	8	10	SYCAMORE
220	0.2	8	12	SYCAMORE
221	0.2	9	12	SYCAMORE
222	0.1	6	8	WILLOW
223	0.1	5	8	S/BIRCH
224	0.2	6	10	CYPRESS

Revision	Description	Date

TOWN AND COUNTRY PLANNING LTD
(020) 8441 4947

13 Evelyn Road, Cockfosters, Hertfordshire EN4 9JT
e-mail: martin@tcpltd.net

Project

Two Storey Side and Rear inc.
Single Storet Rear Extension

45 Kentish Lane
Brookmans Park
Hatfield
AL9 6NG

Client

Mr & Mrs M. Vignali

Topographical Survey

Drawing No.
2012/0730

Scale 1:250 · Drawn By: M.P.M

Checked Y · Date 30 Jan 2013

IMPORTANT NOTICE
© Copyright. Drawing to be used in conjunction with specification and structural engineers notes. Figured dimensions only are to be used. All dimensions to be checked on site prior to commencement of work, differences between drawings, and between drawings and specification or structural engineers details to be referred immediately to Town and Country Planning Ltd. Work should only be undertaken from local authority approved drawings. Commencement of any work on site prior to gaining the necessary planning and or building control approvals is entirely at client's own risk.

ABBREVIATIONS

AB	Air Brick	DH	Duct Height	PRF	Post & Rail Fence
B	Bollard or Bottom	BWP	Down Pipe	PWF	Post & Wire Fence
BB	Belisha Beacon	ECB	Electricity Control	Rbx	Rendar
BD	Back Drop	ELEC	Electricity	RAD	Radius
BH	Borehole or Bean	EP	Electricity Pole	RE	Reading Eye
BM	Bench Mark	FB	Flower Bed	RG	Road Gully
BR	Brick Paviors	FH	Fire Hydrant	RS	Road Sign
BRW	Brick Retaining Wall	FL	Floor Level	RSJ	Rolled Steel Joist
BS	Bus Stop	G	Gully	RWP	Rain Water Pipe
BT	British Telecom	GV	Gas Valve	S	Spread or Stone
BTCB	BT Control Box	H	Height in Metres	SC	Sewer Cover
BU	Bollard Up	HH	Height Head Height	SKL	Skiffle Lantern or Skylight
BWF	Barbed Wire Fence	HT	Height	SP	Arch Springer Height
C	Window Cill Height	IC	Inspection Cover	SPS	Stone Paving Slabs
CB	Control Box	IL	Invert Level	SW	Stone Wall
CBF	Close Boarded Fence	IR	Iron Railing Fence	TCU	Traffic Control
CBW	Concrete Block Wall	IW	Interwoven Fence	T	Top Heights
CCTV	Closed Circuit TV	LO	Locking Outlet	TB	Telephone Box
CIF	Corrugated Iron Fence	LP	Light	TP	Telephone Pole
CL	Cover Level	LP	Lamp Post	TPS	Tactile Paving Slabs
CLF	Chain Link Fence	MH	Manhole	U	Unable To Lift
CLSF	Chain Link Security Fence	MK	Marker	V	Vent
CP	Concrete Pavior	MP	Manhole Cover	VP	Vent Pipe
CPS	Concrete Paving Slabs	OH	Overhead	W	Window
CR	Arch Crown Height	P	Post	WL	Water Level
CRW	Concrete Retaining Wall	PF	Palisade Fence	WM	Water Meter
CSU	Ceiling Slopes Up	PF	Picket Fence	WMF	Wire Mesh Fence
CTV	Cable Television	PIT	Trial Pit	WPF	Wooden Panel Fence
CW	Concrete Wall	PL	Pavement Light	WV	Water Valve
D	Diameter or Doors	PM	Parking Meter	I	Diameter

Top
Banks
Bottom

Drop Kerbs
Overhead Detail
Change in Elevation
Fences
Overhead Cables
Change in Surface
Edge of Vegetation

0.00 Floor to Ceiling Height

0.00 F False Ceiling Height

Gate

Survey Station

Foul Water Sewer
Surface Water Sewer
Combined Sewer

LEVEL NOTE.

COORDINATE SCHEDULE

STN	EASTINGS	NORTHINGS	LEVEL
201	526250.645	204380.159	123.794
202	526237.840	204365.974	123.492
203	526218.052	204431.146	123.674
204	526205.437	204457.050	123.754
205	526187.484	204483.102	123.670
206	526157.928	204517.384	123.502
207	526106.851	204746.930	125.844
208	526101.273	204752.624	125.871
209	526189.399	204722.824	125.872
210	526288.958	204736.311	125.293
211	526255.550	204754.436	124.886
212	526239.190	204692.840	124.617