Appendix D

ROAD SAFETY AUDIT

The Spinney, Essendon: ST16284-1/2



THE SPINNEY HIGH ROAD ESSENDON

SITE ACCESS ARRANGEMENT

STAGE 1 ROAD SAFETY AUDIT

FEBRUARY 2016

GM



Revision Status	Prepared by:	Checked by:	Approved by:	Date Approved:
	(Name)	(Name)	(Signature)	
Original	Mark Barrett	Vimal Patel	Mad Booth.	24 February 2016
Designer's Response				
Authority's Response				
Audit Response		·		

Client: Engineer: JMP GM

Traffic Consultants Ltd

2 Brook Close North Baddesley SO52 9FJ

Date: 24 February 2016



TABLE OF CONTENTS

		ΓΙΟΝ	_
2.0	ITEMS CON	SIDERED	5
3.0 MATTERS ARISING FROM THIS STAGE 1 RSA			6
4.0	AUDITOR S	TATEMENT	7
APF	PENDIX A	Location Plan	
APF	PENDIX A	Location Plan	
APF	PENDIX B	Designers Response	
APF	PENDIX C	Local Highway Authority Response	



1.0 INTRODUCTION

1.1 General

- 1.1.1 This report results from a Stage 1 Road Safety Audit (RSA) carried out on the site access arrangement associated with a new dwelling on the B158 High Road, Essendon.
- 1.1.2 The access will take the form of a vehicle crossover on the eastern side of the B158. Visibility splays have been provided based on the results of a seven day Automatic Traffic Counter (ATC) deployment undertaken in September 2015.
- 1.1.3 The RSA was carried out at the request of JMP.
- 1.1.4 GM Traffic Consultants Ltd carried out the Audit between 19th February and 24TH February 2016. The Auditors were:
 - Mark Barrett
 - V Patel, BEng(Hons), FIHE, HE CoC
- 1.1.5 The Audit Team are independent of the project design team and has had no other involvement with the project.
- 1.1.6 The report has been prepared in accordance with the Design Manual for Roads and Bridges (DMRB) Highways Directive (HD) 19/15.
- 1.1.7 Whilst reference is made to certain design standards, where safety may be compromised by a reduction in standard, this report is not intended to provide a design check. The Auditors have only reported on matters that might have an adverse effect on road safety in the context of the chosen design. No attempt has been made to comment on the justification of the scheme or the appropriateness of the design. Consequently, the Auditors accept no responsibility for the design or construction of the scheme.
- 1.1.8 The Audit consisted of a desktop study and a site visit, which was carried out on Tuesday 23rd February 2016 at 11:15. Traffic flows were light and the weather dry.
- 1.1.9 The recommendations in this report are aimed at addressing the road safety problems; however there may be other alternative acceptable ways to overcome a specific problem, when other practical issues are considered. The recommendations contained herein do not absolve the Designer of his/her responsibilities.

- 1.1.10 The Auditors would be pleased to discuss the acceptability of alternative solutions to problems identified during the Audit, and would encourage the Designer to consult them on this matter.
- 1.1.11 The LHA response to the RSA should be formally recorded and reported to the Designer and the RSA Team so that a record of the Audit process is contained in the As Built design pack to be provided and retained by the LHA on final completion.



2.0 ITEMS CONSIDERED

2.1 The Road Safety Audit was undertaken on the scheme detailed in the following documentation.

Drawing No.	Rev	Title
1511-A-21C	-	Site Plan Proposed Showing Root Protection
ST16284-002	-	Visibility Splay at Revised Access

- 2.2 The Audit Team have been informed of a departure from standards relating to the visibility splay from the proposed access based on the derestricted speed limit.
- 2.3 The visibility splays for a derestricted road cannot be achieved to the south of the access. The results from the ATC undertaken in September 2015 identifies an 85th% speed of 41mph for northbound traffic and 41.8mph for southbound traffic. Based on the 85th% speeds and observations during the site inspection, the Audit Team raise no issues with the proposed visibility splays.



3.0 MATTERS ARISING FROM THIS STAGE 1 RSA

3.1 No road safety issues have been identified following the review of the documents provided and the site inspection.



4.0 AUDITOR STATEMENT

4.1 I certify that this audit has been carried out in compliance with HD 19/15.

AUDIT TEAM LEADER

Mark Barrett

GM Traffic Consultants Ltd

Signed:

TEL: 07787 158 834


AUDIT TEAM MEMBER

Vimal Patel


Signed:

Date: 24 February 2016

APPENDIX A: LOCATION PLANS



Road Safe The Spinney, High Road, Essendon Site Access Arrangement



Road Safe The Spinn Site Acces



APPENDIX B: DESIGNERS RESPONSE

Auditors: Mark Barrett (Team Leader) and Vimal Patel (Team Member).

Scheme: The Spinney, High Road, Essendon - Site Access Arrangement

Date Audit Completed: 24 February 2016

This response is to a Stage 1 Road Safety Audit to the design standard detailed within HD19/15 of Volume 5, Section 2, Part 2, of the Design Manual for Roads and Bridges, as detailed by the Highways Agency.

Problem no.	Problem	Recommended	Alternative measure (detail description)	
in safety	accepted	measure accepted		
audit report	(yes/no)	(yes/no)		
NO ISSUES HAVE BEEN RAISED				



APPENDIX C: LOCAL HIGHWAY AUTHORITY RESPONSE

Principal Engineer's Statement:

Road Safety Audit for The Spinney, High Road, Essendon - Site Access Arrangement

I certify that I have considered the items that have arisen in the Stage 1 Road Safety Audit Report and I am content to accept all of its recommendations except for the ones listed above. I have stated my reasons for not accepting them and I seek the Chief Engineer's endorsement of my proposals.
Date
Principal Engineer

Chief Engineer's Decision:

I accept these proposals by the Principal Engineer.



Date	
Chief Engineer	