



NOTES

- GENERAL

1. All dimensions are in millimetres unless otherwise stated
2. BS 1722 Part 6 applies unless otherwise stated

- MATERIALS

1. All timber shall comply with specification clause 304 and Appendix 3/2
2. All nails and bolts shall comply to BS 729
3. Concrete for post footings to be class C10/P

- CONSTRUCTION

1. Holes for posts will be not less than 300mm square and 600mm deep.
2. Arnis rails will be triangular cut from timber of 75mm x 75mm section.
3. Rails on wooden posts will be driven into the mortices and the top rail only fixed with a 12mm diameter wooden peg.
4. Centre stumps will be splay cut to fit under the bottom rail and will be nailed thereto using one 65mm x 3.35mm galvanized nail.
5. Palisades will be 75 x 20mm spaced 35mm (75mm max.) apart. They will be nailed to each rail with 50mm x 2.65mm galvanized nails using two nails for each rail.

CLIENT: THE GASCOYNE CECIL ESTATES

JOB: BLOODY HOLLOW

BROOKS / MURRAY
 ARCHITECTS
 8-10 NEW NORTH PLACE LONDON EC2A 4JA
 TEL 020 7739 9955 FAX 020 7739 9944
 architects@brooksmurray.com

DRAWING TITLE: WOODEN PALISADE FENCING DETAIL

DATE: APR. 2010

SCALE: N/S

DRAWING NUMBER: 010-DET-001