

SUDS Feature	Regular Maintenance Activity	Frequency	Occasional Maintenance Activity	Frequency	Responsibility
Permeable asphalt Paving	<ul style="list-style-type: none"> Remove debris 	Monthly or as required	<ul style="list-style-type: none"> Sweeping and Brushing 	Annually or as required	School
Inspection Chambers on plot	<ul style="list-style-type: none"> None 		<ul style="list-style-type: none"> Inspect and clean if required 	Annually or as required	School
Pipes and Manholes	<ul style="list-style-type: none"> Visual inspection 	Monthly or as required	<ul style="list-style-type: none"> Cleaning/jetting when silt accumulation occurs 	Annually or as required	School
Gullies	<ul style="list-style-type: none"> Visual inspection 	Monthly or as required	<ul style="list-style-type: none"> Gully pots to be emptied 	Annually or as required	School
Ditches	<ul style="list-style-type: none"> Remove litter Inspect inlets & outlets 	Monthly or as required	<ul style="list-style-type: none"> Remove silt from channels Remove dense vegetation Inlet & outlet cleaning 	Annually or as required	Highway Authority / School pending highway boundary confirmation
Control Structures	<ul style="list-style-type: none"> Inspect control structures for blockages and remove blockage if found 	Monthly or as required	<ul style="list-style-type: none"> Maintenance in accordance with manufacturers recommendations 	Annually or as required	School
Detention Basin	<ul style="list-style-type: none"> Remove litter Inspect inlets & outlets 	Monthly or as required	<ul style="list-style-type: none"> Mow grass to pond edges at 75-100mm Inlet & outlet cleaning Cut back pond vegetation Scrub clearance from bankside 	Annually or as required	School

