



Glazing

Using glazing rebates of 18mm x 53mm, our High Performance DreamVu™ patios will accept either double or triple glazed units. The glazing system is fully drained and vented with a sloping bottom platform. A full 5mm clearance is provided between the insulating glass unit and rebate, in compliance with BS 6262.

Ventilation

The DreamVu™ doorset is supplied as standard without any trickle ventilation installed. This is due to the nature of the developments it is more commonly specified in, such as buildings incorporating heat recovery systems.

Sill Detail

A standard aluminium sill provides a projection of 102mm for open in and 104mm for open out. Care must be taken to ensure that the sill width is suitable for the specified building in detail whilst achieving compliance with Approved Document L, and to allow for internal sill drainage to clear the brickwork. An internal ramp is available if required to achieve compliance with Approved Document M.



Assistance with compliance of Approved Document M available on certain widths.



dB reductions up to: 34dB



U-Value available down to: 1.0 W/m²K

SECTION DETAILS

