

## TZ Wall Mounted Indoor Unit - Split - R32

Product Code: CS-TZ20WKEW

### Wall Mounted - Single Phase- R32

#### Notes

- » Compact and elegant design with only 779mm wide
- » Built-in WLAN for internet and voice control
- » Infrared Sky Controller
- » Cleaner air with PM2,5 filter
- » Super Quiet! Only 20dB(A)
- » More comfort with Aerowings
- » High energy savings



MODEL NUMBER		CS-TZ20WKEW
GRILLE		NA
Nominal cooling (min-max)	kW	2.00 ( 0.75 - 2.40)
Nominal heating (min-max)	kW	2.70 (0.70 - 3.60)
Height	mm	290 x 779 x 209
Width	mm	290 x 779 x 209
Depth	mm	290 x 779 x 209
Weight	kg	8
Knock out for fresh air intake		N/A
Knock out for branch duct		N/A
Indoor unit airflow rate (cool - heat)		365 - 380
Moisture Removal Volume	l/h	1.3
Static pressure	pa	NA
Spigot Kit		N/A
Discharge spigot		NA
Sound pressure level heat (h-m-l)	dB(A)	38 / 26 / 22
Sound pressure level cool (h-m-l)	dB(A)	37 / 25 / 20
Pipe connection size - gas	in	3/8 (9.52)
Pipe connection size - liquid	in	1/4 (6.35)
Refrigerant		R32
Drain connection	mm	VP13 (18mm OD)
Lift pump?		No
Power supply	V-Ph-Hz	From Indoor or Outdoor
Interconnecting cables		3 Core & E
Suggested fuse size		6
Controller included?		Yes - Infrared
* exact cooling and heating capacities will depending on connected outdoor unit and system configuration		