



SU1 SETTLEMENT UNIT 1
 GIA: 195 sqm, 2097 sq ft
 AS: 22, 23
 OPP:



ROOF PLAN
 PLOT 23

PLOT 22



FIRST FLOOR PLAN
 PLOT 23

PLOT 22

NOTES

This drawing to be read in accordance with the specification/Bills of Quantities and related drawings.

No Dimensions to be scaled from this drawing. All stated dimensions to be verified on site and the Architect notified of any discrepancies.

Scale bar 100mm at 1:1

SUBSTRUCTURE NOTES

- Dashed foundation widths are shown as indicative only. Refer to structural engineers site specific foundation plans.
- Foundation depths to be agreed on site with the local building inspector and to conform to NHBC requirements.
- Refer to ground investigation report to establish if radon or any gas measures are required prior to commencement of any site works.
- Drawing to be read in conjunction with coordinated site setting out plan by civil engineer.
- Provide concrete inlets over drains where passing through walls.

WALL CONSTRUCTION LEGEND - HOUSES

External walls - Where shown are to consist of:

- Weatherboard Cladding, in accordance with the External Materials Schedule. On 250mm vertical battens and 250mm counter battens. All over a Breather Membrane.
- Fixed to a Timber Frame Comprising 90mm OSB, 50mm stud with 90mm ACTIS Hybris insulation between the studs and a Vapour Control Layer on the inside face.
- 25mm lathers providing service void and finished with 15mm feature plasterboard to provide 30 minutes fire protection.

Internal walls - Where shown are to consist of:

- 100mm Brickwork, in accordance with the External Materials Schedule, with 50mm cavity, with a Breather Membrane over the face of the 90mm OSB.
- Bricks to a Timber Frame Comprising 90mm OSB, 50mm stud with 90mm ACTIS Hybris insulation between the studs and a Vapour Control Layer on the inside face.
- 25mm lathers providing service void and finished with 15mm feature plasterboard to provide 30 minutes fire protection.

Party walls in accordance with Robust Detail E-WT-2 - Where shown are to consist of:

- 60mm cavity fully filled with mineral wool insulation.
- 90mm OSB sheathing fixed to a Timber Frame comprising of 90mm studs, fully fixed with insulation between the studs and a Vapour Control Layer on the inside face.
- 25mm lathers providing service void and finished with 2 No. Layers of plasterboard to provide 60 minutes fire protection.

Internal Wall - Non Load Bearing Studwork:

- 40x50mm timber studs at 600mm OC fixed with 12.5mm plasterboard lining & 3mm skim to both sides. Void between studs fully filled with mineral insulation (min. 10kg/m³).

Internal Wall - Fire Walls:

- Fully fill between the 40x50mm timber studs with insulation (min. 10kg/m³) to achieve a min. 30 minute fire rating across the wall structure. Face with 15mm fireline plasterboard lining to both sides with 3mm skim finish. Any penetrations through this wall should not compromise the fire rating, see detail 8250-SAU-DET-0206-DR-A-03.

Internal Wall - Load Bearing Studwork:

- Fully fill between the 40x50mm timber studs with insulation (min. 10kg/m³) to achieve a min. 30 minute fire rating across the wall structure. Face with 15mm fireline plasterboard lining to both sides with 3mm skim finish. Any penetrations through this wall should not compromise the fire rating, see detail 8250-SAU-DET-0206-DR-A-03.

Position of Movement Joint Location indicative only - refer to Structural Engineers designs.

CAVITY BARRIER - FIRE STOP

SEPARATING WALL TO EXTERNAL WALL, REFER TO DETAIL 8250-DET-0204-DR-A

SERVICES BOXING LEGEND

SVP and boxing shown as thus to be full height unless AAV. To consist of 38 x 38 mm sw timber batten framed construction and finished with 2no layers 12.5mm plasterboard. SVP to be wrapped with 25mm mineral wool insulation quilt. Refer to 8250-DET-0207-DR-A-01 for information.

Dashed line indicates location of the drainage run, refer to M&E designs for further information.

Services boxing shown as thus to be half height or to suit window cill, to consist of 38 x 38 mm sw timber batten framed construction and finished with 1no layer 15mm Plasterboard.

WALL PENETRATIONS:

Install cavity trays (with stop ends) and weep holes @ 450mm max. c/c to all penetrations through external cavity walls, incl boiler flues, ventilation ducts, etc.

PARTY WALL PENETRATIONS:

All penetrations through party walls must NOT compromise the fire integrity of party wall and should either be fitted with an intumescent sleeve or pass through an intumescent batten. These should be installed in accordance with the manufacturer's instructions. See detail 8250-SAU-DET-0206-DR-A-02 for further information.

THIS WORKING DRAWING IS TO BE READ IN CONJUNCTION WITH THE CONSTRUCTION NOTES, MECHANICAL ENGINEER'S AND STRUCTURAL ENGINEER'S SPECIFICATION & DESIGNS

THIS DRAWING SHOULD BE PRINTED IN COLOUR

C4	Floor layouts amended as per client comments	05/10/21 BW
C3	Ground floor service cupboard added. Plasterboard specification amended	20/11/20 BW
C2	Detail references added/amended	12/11/20 BW
C1	Construction issues	22/10/20 BW
P2	Revised in accordance with client comments	19/10/20 BW
P1	Preliminary issue	14/09/20 BW

CONSTRUCTION

Project
 NORTHAW HOUSE
 COOPERS LANE
 NORTHAW

Title
 SETTLEMENT UNIT 1 PLOT 22-23
 FIRST FLOOR & ROOF PLANS

Scale	Date	11/09/2020
1:50	A1	
1:100	A3	
Drawn	Checked	DR
BW		
Drawing Number	Revision	
8250-SAU-SU1-0003-DR-A	C4	

Saunders
 Architecture + Urban Design