



- KEY**
- Application Boundary
- PAVING**
- P1 Coloured tarmac, pedestrian build up, permeable color 1.b.c
 - P2a Coloured tarmac, vehicular build up, permeable color 1.b.c
 - P2b Coloured tarmac, vehicular build up, impermeable color 1.b.c
 - P3a Wetpour rubber play surface to proposed Splashpad RTD Safety Surfaces Ltd, Classic blend 12 mm thickness on concrete foundation to Ustigate specification
 - P3b Wetpour rubber play surface to proposed Splashpad RTD Safety Surfaces Ltd, Dark blue 12 mm thickness on concrete foundation to Ustigate specification
 - P4 Wetpour rubber play surface to proposed playground RTD Safety Surfaces Ltd, Saiga 20-30 mm thickness dependant on play equipment
 - P5 Tarmacadam finish to compound to Engineer specification
 - P6 Self binding gravel to tree pit, permeable, CED ftd super CEDEC gold
- EDGES**
- E1 Aluminum edge, flush Kinley AluExcel 75 mm flexible edging pinned to concrete foundation
 - E2 Timber edge, flush 150 x 380 mm treated softwood board, 50 x 50 x 450 mm softwood sticks at 500 mm centres
 - E3 Chased edging to play surface 100 mm below finish grass level to prevent shrinkage
 - E4 Concrete pin kerb to compound 50 x 150 x 1600 mm concrete foundation
 - E5 Low retaining wall, 500mm height, vertical timber sleepers in concrete foundation
- FURNITURE**
- F1 Bench to include back and armrest, specification 1.b.c
 - F2 Picnic bench treated softwood, specification 1.b.c
 - F3 Informal seating including logs and timber rounds, sourced from site-own material fixed to concrete foundation
 - F4 Sunshade structure Kompan Cottage ref: NRO207-1001
 - F5 Sunshade structure Kompan Dragon ref: NRO208-1001
 - F6 Bow top fencing re-used from existing play area to break out, repair if necessary, fix to new concrete foundation to suppliers specification
 - F7 Bow top fencing to match F6, allow for radius panels to kiask central space
 - F8 Boundary to secure compound to Architects specification
 - F9 Low headwall to surface water outfall, natural stone facing to all visible edges
 - F10 Proposed bin, specification 1.b.c.
 - F11 Pedestrian gate, Easy-Gate ltd, 1300 mm width, RAL 1003
 - F12 Maintenance gate, Easy-Gate Ltd, 3000 mm width, RAL 1003
 - F13 Cycle stands, stainless steel, specification 1.b.c
- STRUCTURES**
- S1 Refurbished toilet block
 - S2 Proposed refreshment kiosk
 - S3 Existing storage unit to be retained
 - S4 Proposed changing rooms
 - S5 Proposed Splashpad plant enclosure, 12.1 m L x 2.4 m W x 2.38 m H to Ustigate specification
 - S6 Proposed Splashpad dirty water tank, 7.5 m L x 2 m W x 2 m H to Ustigate specification
 - S7 Proposed Splashpad clean water tank, 2.5 m L x 2 m W x 2 m H to Ustigate specification
 - S8 Proposed pump enclosure to Ustigate specification
 - S9 Proposed secure bin storage area
 - S10 Existing electricity substation to be retained
- PLAY EQUIPMENT**
- | Description | Details | Manufacturer |
|---------------------------------------------------------------------------------------------------|---------------------|--------------|
| PE1 Musical pipes play panel | Ref: PCA000708-0603 | Kompan |
| PE2 Dolphin Springer | Ref: NRO111 | Kompan |
| PE3 Butterfly seesaw | Ref: NRO108 | Kompan |
| PE4 Spkca 3 | Ref: GXY8016 | Kompan |
| PE5 Spinner bowl | Ref: ELE400024 | Kompan |
| PE6 Supemova | Ref: GXY916 | Kompan |
| PE7 Five way swing | Ref: NRO903 | Kompan |
| PE8 Robinia explorer ship - X large | Ref: NRO550 | Kompan |
| PE9 Triple combination swing with accessible cradle seat and You&Me seat | Ref: NRO907 | Kompan |
| PE10 Muff spinner carousel | Ref: ELE400060 | Kompan |
| PE11 Forest lake boat with floor | Ref: NRO514 | Kompan |
| PE12 Surprise Basket Goal | Ref: FRE3024-3717 | Kompan |
| PE13 Splashpad water play area refer to Ustigate 'Stamborough Park North_UK_32009_V-0_S2' drawing | | Ustigate |
| PE14 Stepping Pod, Surface level, 0-600 mm | Ref: FAZ30500-0600 | Kompan |
| PE15 Magnetic bells, suspension trainer and muff net | Ref: FAZ20100-0900 | Kompan |
| PE16 Combi 3 | Ref: FSW10300-0901 | Kompan |

turkington martin

Studio 3.05 Chester House, Kennington Park
1-3 Brixton Road, London, SW9 6DE
T: (+44) 020 3567 1050
E: studio@turkingtonmartin.com

CLIENT
Welwyn Hatfield Borough Council

PROJECT TITLE
Splashlands, Stanborough Park

DRAWING TITLE
Materials GA

DRAWING STATUS
For Planning

DRAWING SCALE: 1:250
PAPER SIZE: A1

DRAWN BY: CP
CHECKED BY: JT

DRAWN DATE: 27/03/2019
CHECKED DATE: 27/03/2019

DRAWING NUMBER: TM386L02
REVISION: #

Turkington Martin LANDSCAPE ARCHITECTS

NOTES:

- This drawing is to be read in conjunction with all relevant contract documentation from the design team, with any conflicting information to be brought to the attention of Turkington Martin Landscape Architects in writing before commencing on site.
- The contractor is to check and verify all levels and dimensions before construction. Any discrepancies are to be brought to the attention of Turkington Martin Landscape Architects in writing before commencing on site.
- All dimensions in mm, unless otherwise stated.
- Do not scale from this drawing.
- All sub base and concrete design and specification to engineer's details. All diagrams provided here are purely indicative.
- Waterproofing of any element to be specified by others.
- All proprietary products shall be installed in accordance with manufacturers written instructions.
- Plant numbers are an indication only and plants should be ordered to suit site areas in accordance with scheduled plant schedules.
- Any proposed plant substitution shall be agreed with the landscape architect prior to ordering.