

Creating a sporting habit for life

Comparative Sizes of Sports Pitches & Courts (OUTDOOR)

UPDATED GUIDANCE NON UPDATED GUIDANCE NON UPDATE GUIDANCOOR AND OUTDOOR VERSIONS

September 2015 Update

Introduction

This updated guidance, now with separate documents for indoor and outdoor sports, is intended to give an overview comparison of area requirements for an extended range of outdoor sports.

Following a period of consultation with the National Governing Bodies (NGBs) of sport, the updated information reflects the most up-to-date NGB facility requirements and has been fully endorsed by the NGBs at the time of publication.

This document has been designed to be used in conjunction with NGB guidance (with links provided to the sources of information included) and the Sport England 'User Guide'.

Users should always check with the relevant NGB for their most current criteria which may be updated from time to time.

Feedback from users wishing to report anomalies encountered, such as discrepancies with current or updated NGB criteria, can notify Sport England by email available at:

https://www.sportengland.org/website-feedback/

Contents

Outdoor sports covered in this guidance include the following - those which are new additions are indicated with an *:

Sport	page
American Football	4
Athletics	
Baseball	
Basketball (outdoor)	5
Bowls – Flat Green	
Bowls – Crown Green	6
Cricket	
Football	7
Football: Mini Soccer	
Hockey	8
'in ₂ Hockey' (seven-a-side)	
Lacrosse	9
Outdoor Netball	
Play Touch Rugby League *	10
Rounders	
Rugby League	11
Rugby Union	12
Softball *	13
Tchoukball	
Tennis	14
Wheelchair Rugby League *	
Wheelchair Tennis *	15

Guide to using this document

For sports which have associated downloadable 'Pitch Layouts' available from the Sport England (SE) website, links are provided as examples below:

Click here for SE 'Artificial Grass Pitch Layouts'

Click here for SE 'Natural Turf Pitch Layouts'

See also the 'Design and Cost' section of the SE website for related design guidance including:

- Artificial Surfaces for Outdoor Sports Design Guidance Note
- Natural Turf for Sport Design Guidance Note
- Selecting the Right Artificial Surface

These are available at:

https://www.sportengland.org/facilities-planning/ tools-guidance/design-and-cost-guidance/


The new level of play categories for each sport as agreed by the NGBs and Sport England are:

- **Community** (previously 'Recreational')
- Club (as before)
- **Premier** (previously 'County & Regional')
- (Inter)National (previously 'National & International')

Overall area (O/A) requirements, including dimensions for length and width for each level of play, include the following:

- **PPA** (principal play area); **plus**
- R/O (run offs); plus
- T/O (space for teams (T) and match officials (O)); when required

Where a range of sizes are acceptable for any of the above, minimum (min), preferred (pref) and/or maximum (max) dimensions are listed



			Website		Sport England (SE) weblinks
Level of play category	Community	Club	Premier	(Inter)National	
Area requirements	(L x W)	(L × W)	(L x W)	(L x W)	Notes

American Foot	ball	British American Football	Association (BAFA)	http://www.britishamerica	http://www.britishamericanfootball.org/ and http://rules.bafra.org/rules/rulebook/2014/FieldDiagrams.pdf			
PPA (between	90 yard shortened		all as Community	all as Community	all as Community	All dimensions based on BAFA 'Field dimensions' document.		
end lines)	pitch *	95.10 x 48.77 m pref				See http://rules.bafra.org/rules/field/FieldDimensions.htm		
	100 yard full pitch	104.01 x 46.23 m min				*Shortened pitch dims include min end zones/limit lines.		
		109.73 x 48.77 m pref				**Additional allowance is required for areas to each side of pitch centred on midfield through to both 25 yard lines for:		
O/A **	90 yard shortened	93.61 x 53.16 m min				 Restricted zone: 45.72 x 1.83 m 		
	pitch *	98.76 x 56.09 m pref				 Coaching Box: 45.72 x 1.83 m Team Area: 45.72 x 3.66 m min 		
	100 yard full pitch	110.94 x 53.16 m min				Pitch limit line (R/O) is set 3.66 m generally from the pitch.		
		117.05 x 56.09 m pref				To the rear/sides of the Team Area, the limit line is set at 1.83 m. If space is at a premium, the 1.83 m margin can be		
		(R/O 3.46 m min, 3.66 m ma	ax)			excluded to the rear of the team area.		

Athletics	UK Athletics (UKA)	http://www.ukathletics.net	Click here for SE 'Artificial Sports Surface Layouts'
PPA (see notes adjacent)	All athletics tracks up to premier standar	rd covered by UK Athletics (UKA) are to be designed in accordance with the 'Co	ode of Practice for the Construction and Maintenance of Athletics Tracks
		ne Sports and Play Construction Association (SAPCA) available at <u>www.sapca.</u>	
O/A (see notes adjacent)	•	nd Field Facilities Manual' published by the International Association of Athletics	

s aujacentj

Note and Compact Athletics Facilities documents available at: http://www.sportengland.org/facilities-planning/tools-guidance/design-and-cost-guidance/other-design-guidance/

Baseball		British	Baseball Federation (E	BBF)	www.	britishbaseball.org h	ttp://www.baseballsoftballuk.com/	Click here for SE	'Natura	I Turf Pitch Layouts'
PPA (Diamo	ond) U10	* 18.29 x	18.29 m	all as Community	all as	Community	all as Community	All sizes are metric	conversio	ns of imperical sizes
	U13	3 21.34 x	21.34 m					* U10 category also	includes	PlayBall!
	U16	6 27.43 x	27.43 m							ncluding centre field, home run
	Adul	t 27.43 x	27.43 m					category - see BBF	website a	lepending on age/league/event t: http://www.baseballsoftballuk.
PPA (Diam	ond and U10	60.96 x	60.96 m							ensions and http://www.baseball- ield-maintenance-a-general-guide-
home run)	U13	60.96 x	60.96 m							sions include 18.29 m for foul
	U16	6 76.20 x	76.20 m							but exclude areas beyond the
	Adul	t 99.05 x	99.05 m					centre field on remai	0	an ta danal kali kan Fanas (
O/A (typica	lly) ** U10	* 79.25 x	79.25 m					grandstand 18.29	m from ba	ne to dead ball line. Fence/ ase or foul line. Detailing of ting and batting cage should
	U13	3 79.25 x	79.25 m					be discussed direct	ly with the	NĞB.
	U16	6 94.49 x	94.49 m							rf for Sport Design Guidance
	Adul	t 117.35	x 117.35 m							ortengland.org/facilities-planning/ guidance/natural-turf-for-sport/
Abbreviati	ions:									
	Length x width Metres	incl. excl.	Including Excluding	min max	Minimum Maximum	O/A R/O	Overall space incl. R/O and T/O (see Run off(s): the area outside the court		e unless st	ated otherwise
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officia	ls (O)	N/A	Not applicable

September Revision 006b

OUTDOOR SPORTS	NGB			Website		Sport England (SE) weblinks
Level of play category	Community	Club		Premier	(Inter)National	
Area requirements	(L x W)	(L x W)		(L x W)	(L × W)	Notes
Basketball (outdoor)	Basketball England (BE)			http://www.basketballe	ngland.co.uk	
PPA *	26.0 x 14.0 m min (13.0 x 14.0 m half court) 28.0 x 15.0 m pref	N/A		N/A	N/A	Outdoor Basketball is only played at Community leve Sizes other than as listed may be variable depending o available facility size and should be discussed/agreed wit the NGB.
O/A *	28.1 x 16.1 m min 32.1 x 19.1 m pref	N/A		N/A	N/A	* For outdoor areas that are covered, clear heigh requirements for indoor basketball will apply - see SE 'Basketball' Sports Data Sheet available at:
	(R/O 1.05 m min, 2.05 m pref)					http://www.sportengland.org/facilities-planning/tools-guidance design-and-cost-guidance/sports-halls/
Bowls – Flat Green	Bowls England (BE)			http://www.bowlsengla	nd.com	Click here for SE 'Artificial Grass Pitch Layouts'
PPA	31.0 x 31.0 m min 40.0 x 40.0 m max	all as Communi	ty	all as Community	all as Community	Green size (PPA) allows for 6 no. rinks and excludes the perimeter ditch.
						The green must be either rectangular or square.
Incl. ditch	31.4 x 31.4 m min 40.76 x 40.76 m max					The length of the green in the direction of play must be between 31 m and 40 m.
O/A Incl. ditch and perimeter path	34.4 x 34.4 m min					Play usually rotates N/S and E/W – the green should therefore ideally be equal sided.
	44.76 x 44.76 m max					Rink widths are 4.3 m min, 5.8 m max under World Bowls rules
						The green must be surrounded by a ditch which must be between 0.2 m min and 0.38 m max width and depth from green level of 0.05 m min 0.20 m max.
						Perimeter bank vertical 0.23 m min above green level.
						Perimeter path outside ditch on all sides 1.5 m min, 2.0 m prei
						The green must have a suitable level playing surface tha must be either vegetation or an artificial surface approved by Bowls England. See SEs 'Artificial Fla Green Bowls Briefing Note 2013' available at: http://www.sportengland.org/facilities-planning/tools-guidance/ design-and-cost-guidance/artificial-sports-surfaces/
						For further information on facility requirements, see the World Bowls website at <u>http://www.worldbowls.com/</u> and the following reference documents:
						 World Bowls Introduction to Lawn Bowls World Bowls Laws of the Sport of Bowls World Bowls Performance Standards for Flat Green Bowls Surfaces
Abbreviations:						
m Metres	incl. Including excl. Excluding	min max	Minimum Maximum	O/A R/O	Run off(s): the area outside th	
NGB National Governing Body	PPA Principal play area	pref	Preferred	T/O	Space for teams (T) and matcl	h officials (O) N/A Not applicable

community, club and premier events.

OUTDOOR SPOR	TS NGB		Website		Sport England (SE) weblinks	
Level of play category	Community	Club	Premier	(Inter)National		
Area requirements	(L x W)	(L x W)	(L x W)	(L x W)	Notes	
Bowls – Crown Green	British Crown Green Bo	owling Association (BCGBA)	http://www.crowngreen	bowls.org/		
PPA*	Associations rules and re	gulations. A maximum green siz	in the British Crown Green E ze of 40.0 x 40.0 m is preferred, s	smaller no longer played.	 Proposals for a crown green bowls facility should b discussed with the NGB prior to finalising any design. 	
O/A*	Greens are not divided in	to rinks. The crown height thou and a green can have two c	n size should be considered as 2 gh often 254 mm is variable, it ne rowns. Level of play ranges be	eed not	Perimeter ditch requirements are un-formalised – a 0.3 m wide x 0.125 m deep (below green level) ditch may be acceptable and the ditch should be contained externally by	

Perimeter ditch requirements are un-formalised – a 0.3 m wide x 0.125 m deep (below green level) ditch may be acceptable and the ditch should be contained externally by a raised board top set 100 mm above green level.

Cricket		England and Wales Crick	et Board (ECB)	http://www.ecb.co.uk		Click here for SE 'Natural Turf Pitch Layouts'
PPA	U13 Junior **	6p: 19.20 x 18.30 m	all as Community	as Community	as Community	* All sizes are metric conversions of imperial sizes.
(p = pitch *)	(1p = 19.20 x 3.05 m)	9p: 19.20 x 27.45 m				** Other Junior reduced pitch lengths apply for:
		6p: 20.12 x 18.30 m 9p: 20.12 x 27.45 m 12p: 20.12 x 36.60 m		6p: N/A 9p: 20.12 x 27.45 m 12p: 20.12 x 36.60 m	as Premier	 U9: 16.46 m U10: 17.37 m U11: 18.29 m Boundaries are measured from middle stump of pitch in use:
O/A (p = pitch *)	U13 Junior **	6p: 92.36 x 88.41 m 9p: 92.36 x 97.56 m		as Community	as Community	 Junior 36.58 m (40 yds) Senior: 45.72 m (50 yds) min, 82.26 m (90 yds) max. Tables & wickets to be sited north to south inside 305° and 55°.
	Senior	6p: 111.56 x 106.69 m 9p: 111.56 x 115.84 m 12p: 111.56 x 128.04 m		6p: N/A 9p: 111.56 x 115.84 m 12p: 111.56 x 128.04 m	as Premier	International/Test match boundary requirements should be agreed with the ECB at the early design stages.

Abbrevia	Abbreviations:									
LxW	Length x width	incl.	Including	min	Minimum	O/A	Overall space incl. R/O and T/O (see below) as app	licable unless :	stated otherwise	
m	Metres	excl.	Excluding	max	Maximum	R/O	Run off(s): the area outside the court or pitch (PPA)			
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applicable	

OUTDOOR SPO	RTS NGB		Website		Sport England (SE) weblinks
Level of play category			Premier	(Inter)National	
Area requirements	(L x W)	(L x W)	(L x W)	(L x W)	Notes
Football	The Football Association	(FA)	http://www.thefa.com		Click here for SE 'Natural Turf Pitch Layouts'
PPA	U11/U12: 73.0 x 46.0 m	all as Community	all as Community	National: 100.0 x 64.0 m m	in Click here for SE 'Artificial Grass Pitch Layouts'
	U13/U14: 82.0 x 50.0 m		120.0 x	120.0 x 90.0 m m	
	U15/U16: 91.0 x 55.0 m			International:100.0 x 64.0 m min	Sizes are based on the manufactor hatonal piton sizes
	U17/U18 100.0 x 64.0 m & Senior:			110.0 x 75.0 m m	stated in their 2012 document ' <i>The FA Guide to Pitch and</i> <i>Goalpost Dimensions (Metric</i>)' which include 3 m min wide run offs.
O/A	U11/U12: 79.0 x 52.0 m			Refer to FA guidance	See also FA recommendations for multiple pitches and additional information for additional 'respect' designated spectator area zones.
	U13/U14: 88.0 x 56.0 m				For National and International levels, basic pitch sizes are
	U15/U16: 97.0 x 61.0 m				based on the FAs Laws of the Game 2014-15 available at http://www.thefa.com/my-football/referee/laws-of-the-game
	U17/U18 106.0 x 70.0 m				Detailed discussions with the NGB should take place at the
	& Senior:				design stage of any project incorporating a football facility.
	(All R/O 3.0 m min)				See also FA weblink <u>http://www.thefa.com/my-football/</u> football-volunteers/runningaclub/yourfacilities/

Football: Mini Soccer	The Football Association (FA)	http://www.thefa.com	Click here for SE 'Natural Turf Pitch Layouts'
PPA *	U7/U8: 37.0 x 27.0 m all as Community U9/U10: 55.0 x 37.0 m	all as Community all as Community (National only)	Click here for SE 'Artificial Grass Pitch Layouts'
0/A *	U7/U8: 43.0 x 33.0 m U9/U10: 61.0 x 43.0 m		* PPA and O/A sizes are based on the FAs updated national pitch sizes stated in their 2012 document ' <i>The FA Guide to</i> <i>Pitch and Goalpost Dimensions (Metric</i>)' which include 3 m min wide run offs.
	(All R/O 3.0 m min)		See also FA recommendations for multiple pitches and additional information for additional 'respect' designated spectator areas zones.
			International play is currently outside FIFA rules – and subject to individual NGB's. There have been no England International games and limited National play.

Abbreviations:									
LxW m	Length x width Metres	incl. excl.	Including Excluding	min max	Minimum Maximum	R/O	Overall space incl. R/O and T/O (see below) as applicable Run off(s): the area outside the court or pitch (PPA)		
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applicable

OUTDOOR SPORTS	NGB		Website		Sport England (SE) weblinks
Level of play category	Community	Club	Premier	(Inter)National	
Area requirements	(L x W)	(L × W)	(L x W)	(L x W)	Notes

Hockey	England Hockey (EH)		http://www.englandhockey.co.u	<u>k/</u>	Click here for SE 'Artificial Grass Pitch Layouts'
ρρα	91.4 x 55.0 m 97.4 x 59.0 m min	all as Community	all as Community	all as Community	Sizes are based upon International Hockey Federation (FIH) document <i>Rules of Hockey (January 2013)</i> available at: http://www.englandhockey.co.uk/page.asp?section=1146&se
	101.4 x 63.0 m pref				<u>ctionTitle=Rules+of+Hockey</u> . * For minimum run offs, a 1.0 m width of the side R/O
	(R/O: 2.0 m sides, 3.0 m ends mir	ı			and 2.0 m width of the end R/O (adjacent to the PPA) must be of the same playing surface as the PPA.
	and 4.0 m sides, 5.0 m ends pref)	*			For preferred run offs, a 3.0 m width of the side and end R/O's (adjacent to the PPA) must be of the same playing surface as the PPA.

'in ₂ Hockey' (Seven-A-Side)	England Hockey (EH)		http://www.englandhockey.co.u	<u>ik/</u>	Click here for SE 'Artificial Grass Pitch Layouts'
PPA O/A	55.0 x 43.0 m (O/A: see notes adjacent*)	all as Community	all as Community	all as Community	*Sizes for 'in ₂ Hockey' (formerly known as 'mini hockey') are based upon two pitches (with full size D's and goals) running transversely across a full-size FIH pitch (see 'Hockey' criteria above).
	(R/O: subject to main pitch R/O dimensions**)				** EH do not provide specific safety run off (R/O) criteria for in ₂ Hockey but are generally established by full pitch R/O provision. 5.0 m is the minimum R/O requirement between pitches.
					See 'Hockey' criteria above regarding the width of the side and end R/O's (adjacent to the PPA) that must be of the same playing surface as the PPA.
					For further information, see EH's <i>in₂Hockey Advisory Guidelines</i> available at <u>http://in2hockey.englandhockey.</u> <u>co.uk/game-guidelines.aspx</u> .

Abbrevia	Abbreviations:											
LxW	Length x width	incl.	Including	min	Minimum	O/A	Overall space incl. R/O and T/O (see below) as ap	olicable unless	stated otherwise			
m	Metres	excl.	Excluding	max	Maximum	R/O	Run off(s): the area outside the court or pitch (PPA)				
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applicable			

September Revision 006b

OUTDOOR SPO	RTS NGB		Website		Sport England (SE) weblinks
Level of play category	Community	Club	Premier	(Inter)National	N .
Area requirements	(L x W)	(L x W)	(L x W)	(L x W)	Notes
Lacrosse	English Lacrosse Associ	ation (ELA)	http://www.englishlacrosse.	co.uk/english-lacrosse-ngb/	
PPA *	91.4 x 55.0 m min *** 110.0 x 60.0 m pref	all as Community	all as Community ****	all as Community ****	* As of September 2015 all English Lacrosse pitches mus conform to the new Federation of International Lacrosse (FIL) <i>Unified Pitch Markings</i> with the same PPA and O/A sizes for both men and women categories, but with respective line marking variations.
O/A **	97.4 x 67.0 m min *** 116.0 x 72.0 m pref				** O/A sizes include a 3.0 m minimum run off (R/O) to al sides generally and an additional 6.0 m (partially) along one side providing 9.0 m in total for T/O beyond PPA.
	(R/O 3.0 m min)				*** FIL has developed a set of measurements for existing fields below preferred PPA sizes. Minimum sizes stated ar based on an International Hockey Federation (FIH) field
	(incl. additional 6.0 m for T/C))*****			hockey pitch. However, further criteria for shorter on narrower pitches is also available at http://www.englishlacrosse.co.uk/lacrosse-rules-and-regulations/ and http://tilacrosse.com/rules-field-dimensions/ .
					**** For Premier and International levels, an artificial grass pitch (AGP) is the preferred surfacing.

***** For Community and Club level T/O criteria, see http://www.englishlacrosse.co.uk/clubs-university-lacrosse/.

Adjacent pitches (PPAs) should be separated by 6.0 m min.

Outdo	or Netball	Englar	nd Netball (EN)			http://www.england	inetball.co	<u>o.uk/</u>	Click here for SE	'Artificia	I Sports Pitch Layouts'
PPA *		30.5 x	15.25 m	as Community		N/A ***		N/A ***	30.5 x 15.25 m. V	Vhen there	yed on all courts (PPA) that are s insufficient space for a full size
0/A *		34.5 x	18.25 m	34.5 x 18.25-20	.25** m min						ffs, a formal risk assessment y operator can establish if
				36.6 x 21.35-23	.35** m pref						on may be allowed with the court t with reduced run offs - see SE's
		(1.5 m	side R/O and	(1.5 m side R/O	and				Netball Design Gu	uidance No	te.
		2.0 m	end R/O)	2.0 m end R/O	min						y-side with no division fencing
				3.05 m R/O to a	ll sides pref)				/ 2.0-4.0 m (club)		nmon run off 2.0 m (community) can be used.
		(T/O n	ot required)	(incl./excl. 2.0 m T/O)	n for optional				above the PPA as offs, the inner edg	s for indoo ge of struct	n min clear height is required r netball criteria. Above the run ure/fittings can reduce from 7.5 o 4.5 m min at the lowest point.
									** Width range de match officials (T		n inclusion of optional team and
											hampionships are now played combined elastic floors.
Abbrevia	itions:										
LxW m	Length x width Metres	incl. excl.	Including Excluding	min max	Minimum Maximum	0/ R/		Overall space incl. R/O and T/O (see Run off(s): the area outside the court		ole unless	stated otherwise
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	Τ/	0	Space for teams (T) and match official	s (O)	N/A	Not applicable

September Revision 006b

9

80.0 x 54.0 m min

90.0 x 54.0 m pref

5.0 m min - 10.0 m max

2.0 m min (to sides only)

OUTDOOR SPORT	S NGB		Website		Sport England (SE) weblinks
Level of play category	Community	Club	Premier	(Inter)National	
Area requirements	(L x W)	$(L \times W)$	(L × W)	(L x W)	Notes
Play Touch Rugby League	Rugby Football League	• (RFL)	http://www.therfl.co.uk	<u>/index.php</u>	
PPA (Basic pitch) *	70.0 x 50.0 m pref	all as Community	N/A	N/A	RFL refer to the following key areas (Sport Englan- equivalents/abbreviations indicated in brackets):
PPA plus In-goal (I/G) areas (Playing area) **	80.0 x 50.0 m min 90.0 x 50.0 m pref				 Field of play (PPA - basic pitch) In-goal (I/G) Playing area (PPA - basic pitch incl. I/G)

- Run offs (R/O)
- Playing enclosure (O/A)

* PPA basic pitch sizes taken between goal lines.

** PPA playing area including in-goal (I/G) areas beyond each end of basic pitch as indicated for the respective categories. The length and breadth of the total PPA are to be as near as possible to the preferred dimensions indicated.

*** O/A includes PPA playing area including in-goal (I/G) areas and safety run off (R/O) margins as indicated. O/A excludes any provision for T/O or spectator viewing.

See RFL Rugby League Pitch Dimensions document available at http://www.rflfacilitiestrust.co.uk for pitch criteria.

For further information, refer to RFL's *Play Touch Rugby League Facility Guidance* available at: http://www.playtouchrugbyleague.co.uk/

Rounders			Rounders England (RI	Ξ)	http://	www.roundersengla	nd.co.uk/	
PPA *			20.0 x 12.0 m 20.0 x 12.0 m	all as Community	all as	Community	all as Community	* The PPA should not be placed in corners which will restrict the forward hitting area.
0/A **		Junior 6	60.0 x 40.0 m min					** Play usually takes place without boundaries, but if one is required: adults 50 m and juniors 30 m, measured from front right corner of batting square.
		Senior	100.0 x 60.0 m min					In any multi-pitch layout, 10 m is required between pitches.
		1	Note: Junior level PPA i	s under review at the time o	f publication - refer t	o RE website for c	urrent status.	See RE guidance and Official Rounders Rules available from http://www.roundersengland.co.uk/play/rules/ .
Abbreviation	ns:							
LxW L	ength x width	in	ncl. Including	min M	/ linimum	O/A	Overall space incl. R/O and T/O	D (see below) as applicable unless stated otherwise

LxW	Length x width	incl.	Including	min	Minimum	O/A Overall space incl. R/O and T/O (see below) as applicable unless stated otherwise
m	Metres	excl.	Excluding	max	Maximum	R/O Run off(s): the area outside the court or pitch (PPA)
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O Space for teams (T) and match officials (O) N/A Not applicable

September Revision 006b

O/A ***

In-goal (I/G) criteria

Run off (R/O) criteria

OUTDOC	OR SPORTS	NGB		Website		Sport England (SE) weblinks	
Level of play cate	gory	Community Club		Premier	(Inter)National		
Area requirement	S	(L × W)	(L × W)	(L x W)	(L x W)	Notes	
Rugby League	9	Rugby Football League (RFL)	http://www.therfl.co.uk/	/index.php	Click here for SE 'Natural Turf Pitch Layouts'	
PPA	U7/U8/U9:	50.0 x 30.0 m min	all as Community	N/A	all as Premier	Click here for SE 'Artificial Grass Pitch Layouts'	
(Basic pitch) *		60.0 x 40.0 m pref					
	U10/U11 (11-a-side):	80.0 x 50.0 m pref		N/A		RFL refer to the following key areas (Sport Englan equivalents/abbreviations indicated in brackets):	
	U12-Adult (11-a-side):	92.0 x 55.0 m min		N/A		 Field of play (PPA - basic pitch) 	
	U12-Adult:	100.0 x 68.0 m pref		as Community		 In-goal (I/G) Playing area (PPA - basic pitch incl. I/G) 	
PPA plus In-goal	U7/U8/U9:	N/A - no IGs		N/A		 Run offs (R/O) Playing enclosure (O/A) 	
(I/G) areas	U10/U11 (11-a-side):	N/A - no IGs		N/A		, , ,	
(Playing area) **	U12-Adult (11-a-side):	104.0 x 55.0 m min		N/A		* PPA basic pitch sizes taken between goal lines.	
	U12-Adult:	116.0 x 68.0 m pref		as Community		** PPA playing area including in-goal (I/G) areas beyon each end of basic pitch as indicated for the respectiv categories. The length and breadth of the total PPA are t	
0/A ***	****U7/U8/U9:	54.0 x 34.0 m min 64.0 x 44.0 m pref		N/A		be as near as possible to the preferred dimension indicated.	
	U10/U11 (11-a-side):			N/A		*** O/A includes PPA playing area including in-goal (I/C	
	U12-Adult (11-a-side):	·		N/A		areas and safety run off (R/O) margins as indicated for th	
	(,	116.0 x 74.0 m pref		as Community		respective categories. O/A excludes any provision for T/0 or spectator viewing.	
	012-Addit.	110.0 x 74.0 m pier		as community			
						See RFL Rugby League Pitch Dimensions documer available at http://www.rflfacilitiestrust.co.uk for pitch criteria	
In-goal (I/G) criteria				N/A			
	U12-Adult (11-a-side): U12-Adult:			N/A as Community		Where multiple pitches are to be laid out in close proximit there is a requirement for a space of three metres betwee the outside lines of the run off areas. This is for both safet and to accommodate spectators.	
Run off (R/O)	U7-U11:	2.0 m (to all sides)		N/A		There is no requirement for additional space betwee	
criteria		2.0 m (to long sides only)		N/A		in-goal areas other than to accommodate spectators an it is therefore discretionary.	
	()	3.0 m (to long sides only)		as Community		it is therefore discretionary.	

Abb	reviation	IS:								
LxV	N Le	ength x width	incl.	Including	min	Minimum	O/A	Overall space incl. R/O and T/O (see below) as applicable	e unless st	ated otherwise
m	Me	etres	excl.	Excluding	max	Maximum	R/O	Run off(s): the area outside the court or pitch (PPA)		
NGE	3 Na	ational Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applicable

September Revision 006b

OUTDOC	OR SPORTS	NGB		Website		Sport England (SE) weblinks
Level of play cate	egory	Community	Club	Premier	(Inter)National	
Area requiremen	ts	(L x W)	(L x W)	(L × W)	(L x W)	Notes
Rugby Union		Rugby Football Union (RF	U)	http://www.englandrugby	<u>y.com/</u>	Click here for SE 'Natural Turf Pitch Layouts'
PPA	U7:	20.0 x 12.0 m max/pref	N/A	N/A	N/A	Click here for SE 'Artificial Grass Pitch Layouts'
(Basic pitch) *	U8:	45.0 x 25.0 m max/pref	N/A	N/A	N/A	
	U9:	60.0 x 35.0 m max/pref	N/A	N/A	N/A	RFU refer to the following key areas (Sport England
	U10:	60.0 x 35.0 m max/pref	N/A	N/A	N/A	equivalents/abbreviations indicated in brackets):
	U11/U12:	60.0 x 43.0 m max/pref	N/A	N/A	N/A	 Field of play (PPA - basic pitch)
	Senior 7/10/15-a-side:	100.0 x 70.0 m max/pref	as Community	as Community	94.0 x 68.0 m min	 In-goal (I/G)
					100.0 x 70.0 m pref	 Playing area (PPA - basic pitch incl. I/G) Perimeter area (safety run offs - R/O)
						 Perimeter area (safety run offs - R/O) Playing enclosure (O/A)
PPA plus In-goal (I/G) areas		30.0 x 12.0 m max/pref	N/A	N/A	N/A	
(Playing area) **		55.0 x 25.0 m max/pref	N/A	N/A	N/A	* PPA basic pitch sizes taken between goal lines.
(Flaying alea)		70.0 x 35.0 m max/pref	N/A	N/A	N/A	** PPA playing area including in-goal (I/G) areas beyond
		70.0 x 35.0 m max/pref	N/A	N/A	N/A	each end of basic pitch as indicated for the respective
	U11/U12:	70.0 x 43.0 m max/pref	N/A	N/A	N/A	categories. The length and breadth of the total PPA are to be as near as possible to the preferred (pref) dimensions
	Senior 7/10/15-a-side:	144.0 x 70.0 m max	as Community	as Community	106.0 x 68.0 m min	indicated.
					144.0 x 70.0 m max	*** O/A includes PPA playing area (incl. I/G areas) and
0/4 ***	117.	00 0 v 10 0 m min	N1/A	N1/A	N1/A	perimeter areas (R/O) as indicated for the respective
O/A ***	-	36.0 x 18.0 m min	N/A	N/A N/A	N/A	categories. O/A excludes any provision for T/O or spectator viewing. Where the max/pref dimensions cannot be
		61.0 x 31.0 m min	N/A	N/A N/A	N/A	achieved, appropriate dimensions should be identified on
		76.0 x 41.0 m min	N/A	N/A N/A	N/A	a site by site basis using a common sense approach based
		80.0 x 45.0 m pref	N/A		N/A	upon the type, level and intensity of rugby activity that will take place.
		80.0 x 53.0 m pref	N/A	N/A	N/A	
	Senior 7/10/15-a-side:	154.0 x 80.0 m max	as Community	as Community	116.0 x 78.0 m min	**** Adjacent U7-U9 pitches should be min 5.0 m apart.
					154.0 x 80.0 m max	***** Where the required 5.0 m run off is not deemed
In-goal (I/G) criteri	ia U7-U12:	5.0 m	N/A	N/A	N/A	'practicable', an appropriate run off should be identified by undertaking a comprehensive risk assessment based upon
		6.0 m min - 22.0 m max	as Community	as Community	as Community	the type, level and intensity of rugby activity and the
	Senior 7/10/15-a-Side.	0.0 m mm - 22.0 m max	as Community	as Community	as Community	surrounding physical environment.
						For further information on full-size pitch criteria for Senior
Perimeter area (R/O) criteria		3.0 m min ****	N/A	N/A	N/A	levels of play and general requirements, see the updated World Rugby Laws of The Game available from their
(ivo) criteria		5.0 m min *****	N/A	N/A	N/A	website at http://laws.worldrugby.org/?section=5
	Senior 7/10/15-a-side:	5.0 m min *****	as Community	as Community	as Community	nosono at <u>maji / ano nonalago / osonon-o</u>

Abbreviations:									
LxW	Length x width Metres	incl. excl.	Including Excluding	min max	Minimum Maximum	O/A Overall space incl. R/O and T/O (see below) as applicable unless stated otherwise R/O Run off(s): the area outside the court or pitch (PPA)			
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O Space for teams (T) and match officials (O) N/A Not applicable			

September Revision 006b

OUTDOOR SPORTS	NGB		Website		Sport England (SE) weblinks
Level of play category	Community	Club	Premier	(Inter)National	
Area requirements	(L × W)	(L x W)	$(L \times W)$	(L × W)	Notes

Softball - fastpitch	ı (fp) / slowpitch (sp)	British Softball Federation (B	SF)	http://www.britishsoftball.org/	http://www.baseballsoftballuk.com/	Click here for SE 'Natural Turf Pitch Layouts'
PPA (Diamond)	U10* (fp):	16.76 x 16.76 m	all as Community	all as Community	all as Community	All sizes are metric conversions of imperical sizes.
	U12 (fp):	18.29 x 18.29 m				* U10 category also includes PlayBall!
	U14 (fp):	18.29 x 18.29 m				Dimensions are based on women and girls fastpitch and
	Over 14 / Adult (fp):	18.29 x 18.29 m				mixed/co-ed slowpitch. Dimensions for men's fastpitch or slowpitch should be discussed directly with the NGB
	Over 14 / Adult (sp):	19.81 x 19.81 m				category. For further information, see BSF website at:
PPA (Diamond and	U10* (fp):	60.96 x 60.96 m				http://www.baseballsoftballuk.com/document/softball-field-
home run)	U12 (fp):	67.06 x 67.06 m				dimensions . O/A dimensions include 9.14 m for foul line to fence line on
	U14 (fp):	67.06 x 67.06 m				two sides but exclude areas beyond the centre field on
	Over 14 / Adult (fp):	67.06 x 67.06 m				remaining sides.
	Over 14 / Adult (sp):	83.82 x 83.82 m				Minimum 7.62 m from foul line to dead ball line. Fence / grandstand 9.14 m from base or foul line. Detailing of bases,
O/A	U10* (fp):	70.10 x 70.10 m				fencing/ball arrest netting and batting cage should be discussed directly with the NGB.
	U12 (fp):	76.20 x 76.20 m				See Sport England Natural Turf for Sport Design Guidance
	U14 (fp):	76.20 x 76.20 m				Note available at http://www.sportengland.org/facilities-planning/
	Over 14 / Adult (fp):	76.20 x 76.20 m				tools-guidance/design-and-cost-guidance/natural-turf-for-sport/
	Over 14 / Adult (sp):	92.96 x 92.96 m				

Tchoul	kball	Tchoul	kball UK (TUK)		<u>h</u>	ttp://www.tchoukball.org	<u>j.uk/</u>			
PPA*			11.0 m min 13.0 m pref	all as Commun	ty a	II as Community	all as Community		rts or on g	utdoors, typically on the beach, grass, as well as indoors (see of this guidance).
O/A*		25.0 x	16.0 m min					Outdoor Tchoukk	all is typic	ally played 5-a-side.
			18.0 m pref 0 m min)							or indoor Tchoukball and are played in 3 sets with each set to
		(T/O 1.	0 m min to one side)					21.0 x 11.0 m an	d 23.0 x 10 ace for rur	vels can be anywhere between 3.0 m depending on the venue n off (R/O) and teams/officials
								R/O requirements are 2.0 m min (to all sides)		n min (to all sides)
								** O/A sizes inclu T/O.	de an addi	itional 1.0 m along one side for
								Each shooting 'I radius of 3.0 m.	D' is mark	ed out with cones and has a
Abbrevia	ations:									
LxW m NGB	Length x width Metres National Governing Body	incl. excl. PPA	Including Excluding Principal play area	min max pref	Minimum Maximum Preferred	0/A R/O T/O	Overall space incl. R/O and T/O Run off(s): the area outside the c Space for teams (T) and match off	ourt or pitch (PPA)	ole unless : N/A	stated otherwise Not applicable

00	0/(0/.	Excluding	THOUS	i i i a i i i a i i i a i i i a i i i a i i i a i i i a i i a i i a i i a i i a i i a i i a i i a i i a i i a i	100			
onal Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applica

OUTDOOR SPO	RTS NGB		Website		Sport England (SE) weblinks	
Level of play category	Community	Club	Premier	(Inter)National		
Area requirements	(L x W)	(L x W)	(L x W)	(L x W)	Notes	
Tennis	Lawn Tennis Associatio	Lawn Tennis Association (LTA)			Click here for SE 'Artificial Grass Pitch Layouts'	
PPA *	23.77 x 10.97 m	all as Community	all as Community	all as Community	* PPA sizes indicated are for a standard doubles court.	
O/A	34.75 x 17.07 m min 36.57 x 18.29 m pref				A shared run off between adjacent courts is 3.66 m min or 4.27 m pref (e.g. a two-court area would be 34.75 x 31.77 m min or 36.57 x 33.53 m pref.	
	(R/O min: 3.05 m sides, 5.49 m ends R/O pref: 3.66 m sides, 6.40 m ends)				See LTA document 'Key tennis dimensions' available at: http://www3.lta.org.uk/clubs-schools/Resourcesfacility-guidance/	

Wheelchair Rugby League	Rugby Football League (R	IFL)	http://www.therfl.co.uk/ind	dex.php http://www.wheelchairrl.c	o.uk/
PPA (Basic pitch) *	38.0 x 18.0 m min 40.0 x 20.0 m pref	all as Community	all as Community	all as Community	Wheelchair Rugby League play can take place on bot indoor and outdoor facilities which have appropriat surfaces for sports chair use.
	45.0 x 22.0 m max				* PPA basic pitch sizes taken between goal lines.
PPA plus In-goal (I/G) areas	42.0 x 18.0 m min				** PPA playing area including in-goal (I/G) areas beyor
(Playing area) **	45.0 x 20.0 m pref				each end of basic pitch as indicated for the respectiv
	50.0 x 22.0 m max				categories. The length and breadth of the total PPA are to be as near as possible to the max/pref dimension
D/A ***	46.0 x 22.0 m min				indicated.
	49.0 x 24.0 m pref				*** O/A includes PPA playing area including in-goal (I/C areas and safety run off (R/O) margins as indicated. O/
	54.0 x 26.0 m max				excludes any provision for T/O or spectator viewing.
n-goal (I/G) criteria	2.0 m min - 2.5 m max				See RFL Rugby League Pitch Dimensions docume available at http://www.rfifacilitiestrust.co.uk for pitch criteri
Run off (R/O) criteria	2.0 m (to all sides)				Post height 4 to 5 m, post width apart: 3 m, crossbar heigi above floor: 2 m.
					Surface must be hard, level and consistent to ensure good safe running for wheelchairs.
					The centre, 4 and 8 metre lines must be clearly marke using (1) adhesive tape (on floor), (2) paint (on concrete) of (3) plastic cones or domes (placed 1 m outside touch lines)
					For further information, refer to Wheelchair Rugby Leagu Laws of the Game available at:
					http://www.wheelchairrl.co.uk/downloads
Abbreviations:					
xW Length x width	incl. Including	min Minim	um O/A	Overall space incl. R/O and T/O	O (see below) as applicable unless stated otherwise

Abbrevi	Abbreviations:									
L×W	Length x width	incl.	Including	min	Minimum	O/A	Overall space incl. R/O and T/O (see below) as app	licable unless	stated otherwise	
m	Metres	excl.	Excluding	max	Maximum	R/O	Run off(s): the area outside the court or pitch (PPA)			
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applicable	

OUTDOOR SPO	RTS NGB		Website		Sport England (SE) weblinks			
Level of play category	Community	Club	Premier	(Inter)National				
Area requirements	(L x W)	(L × W)	(L x W)	(L x W)	Notes			
Wheelchair Tennis	Lawn Tennis Associatio	on (LTA)	http://www.lta.org.uk		Click here for SE 'Artificial Grass Pitch Layouts'			
PPA (as for tennis)	For court information, se	e criteria for Tennis above.						
	Wheelchair tennis integrates very easily with the non-disabled game since it can be played on any regular tennis court, with no modifications to rackets or balls. Wheelchair tennis playe are allowed two bounces of the ball and can play against other wheelchair tennis players as well as alongside or against non-disabled friends and family.							
O/A (as for tennis)	For further information s	ee: http://www.lta.org.uk/Tenr	tp://www.lta.org.uk/Tennis-Foundation/Tennis-for-Disabled-People/					

Abbrevi	Abbreviations:									
LxW	Length x width	incl.	Including	min	Minimum	O/A	Overall space incl. R/O and T/O (see below) as ap	olicable unless s	stated otherwise	
m	Metres	excl.	Excluding	max	Maximum	R/O	Run off(s): the area outside the court or pitch (PPA)		
NGB	National Governing Body	PPA	Principal play area	pref	Preferred	T/O	Space for teams (T) and match officials (O)	N/A	Not applicable	



-		-	
	-		

Alternative Languages and Formats:

This document can be provided in alternative languages, or alternative formats such as large print, Braille, tape and on disk upon request.

Call the Sport England switchboard on 08458 508 508 for more details.

Prepared by:

Sport England and Abacus Cost Management Ltd (Design Services)

Acknowledgements:

Sport England thank the National Governing Bodies of Sport for their contribution to this guidance and MSc - Consultants for photographic material.

User Guide:

Before using this design guidance note for any specific projects all users should refer to the *User Guide* to understand when and how to use the guidance as well as understanding the limitations of use.

Click here for 'User Guide'

Click here for current 'Design and Cost Guidance'

Issue Tracker:

- 006a/b Updates and reformatting into separate indoor/outdoor documents: September 2015
- 005 Updates to Indoor Basketball court/run-off sizes / Outdoor Football: April 2011
- 004 Updates to indoor court sizes, hyperlinks, NGB's and rebranding: February 2009
- 003 Third Issue: July 2007
- 002 Consultation issue: April 2007
- 001 Initial Publications: July 2006

Sport England

1st Floor, 21 Bloomsbury Street London WC1B 3HF

Tel : +44 (0)8458 508 508

Further Information:



© Sport England, September 2015

To find out more about Sport England and to get the latest news and information about our various initiatives and programmes, please go to www.sportengland.org