



IMPERIAL
handmade bricks

TECHNICAL INFORMATION

BRICK NAME	CATEGORY 4 COMPRISING OF: Farmhouse Orange Country Blend / 2" Country Blend ⁺⁺ Olde Reclamation Clamp Urban Weathered Tudor Multi Brick/Paver ⁺⁺
BRICK TYPE	Through colour clay handmade brick
SPECIFICATION	Manufactured to BS EN 771-1
SIZE*	230 x 110 x 68mm ⁺ 215 x 102.5 x 65mm ⁺⁺ 230 x 110 x 50mm
DIMENSIONAL TOLERANCE:	T1
RANGE:	R1
COMPRESSIVE STRENGTH	Mean - 30 N/MM ²
WATER ABSORPTION	Mean - 15%
SOLUBLE SALT CLASSIFICATION	S2
BULK DENSITY	1600 kg/m
PACKAGING	Shrink wrapped on wooden pallets in packs of 525/ ⁺ 650/ ⁺⁺ 600
PACK SIZE; LxWxH	1100 x 1100 x 1100mm Approx.
PACK WEIGHT	1.5 Tonnes Approx.
USAGE	Always mix from several packs, working vertically down the blades, not horizontally across the tops of the packs
SAMPLES	Samples will be supplied on request.
DURABILITY	F2
PERFORMANCE	The recommendations of good practice made in the relevant British Standards regarding design and workmanship must be fully observed. Liability cannot be accepted for the performance of the product if used outside our recommendations. Guidance on the use of these bricks in specific situations is readily available from us.

*Individual bricks may vary dimensionally; this is a natural characteristic of fired clay bricks and is catered for in the relevant European Standard.

05.2020

