The

## Heritage Clay Tiles Ltd Clayhall

Range



## Clayhall Medium Blend

Carefully crafted to replicate all the features of handmade clay tiles, the Clayhall hand crafted range of tiles offers an excellent alternative when budget restrictions are a concern, but without compromising quality or durability.

Description	Roof	Vertical
Minimum Roof Pitch	35°	75°
Headlap (Minimum)	65mm	38mm
Batten Spacing at Maximum Gauge	100mm	114mm
Size of Tile	265 x 165mm	265 x 165mm
Covering Capacity	60 per m2	53 per m2
Cover Width	265 x 165mm	265 x 165mm
Weight as Laid	75kg per m2	66.25kg per m2
Battens per M2	10m	8.7m
Batten Size	38 x 25mm	38 x 25mm
Recomended Nail Type	40 x 2.65mm Alloy Clout	40 x 2.65mm Alloy Clout

Heritage Clay Tiles Ltd Hangman's Wood Ind Park Stifford Road, South Ockendon Essex RM15 6RL tel: 01708 853 953 fax: 01708 851 852 email: sales@heritagetiles.co.uk website: www.heritagetiles.co.uk