

# The Walled Garden

## LEGEND

### Soft Landscape

- Existing Trees Retained
- Proposed Tree Planting
- Proposed Ornamental Shrub Planting
- Proposed Pleached Tree Screen
- Proposed Specimen Shrubs
- Proposed Vegetable Patch
- Proposed Low Ornamental Hedging
- Proposed hornbeam Hedge
- Proposed Clipped Native Hedging
- Proposed Topiary Spheres
- Proposed bulbs
- Proposed Amenity Grass

### TREE PLANTING

Code	Species	Form	Girth cm	Height cm	Plant condition	Quantity
ACE	Acer campestre 'Eclairj'	Select Standard	10-12	Min 250-300cm	RB	2
BP	Betula pendula	EHS	14-16	425-600cm	65/85 L	4
BLJD	Betula utilis Jacquemonti Douerensis	Multi-stemmed	-	425-600cm	100-125L	2
CP	Carpinus betulus (Pleached)	EHS 1.5m clear stem, 4 tiers	14-16	300-350	45 L	6
CPFF	Carpinus betulus 'Franz Fontaine'	EHS	14-16	425-600cm	45 L	6
FS	Fagus sylvatica f. purpurea	EHS	14-16	425-600cm	65/85 L	3
LQS	Liquidamber styraciflua Lane Roberts'	EHS	14-16	425-600cm	65/85 L	3
PRSH	Prunus 'Shirofugen'	Select Standard	10-12	Min 250cm	RB	2
SCE	Sorbus commixta 'Embley'	EHS	14-16	425-600cm	65/85 L	4
TXB	Taxus baccata 'Fastigiata'	EHS	14-16	425-600cm	65/85 L	1
TGT	Taxus baccata	EHS	14-16	425-600cm	65/85 L	2
TCG	Tilia cordata Greenspire	EHS	14-16	425-600cm	RB	4
QR	Quercus robur	Select Standard	10-12	Min 250cm	RB	5
GRU	Quercus rubra	Select Standard	10-12	Min 250cm	RB	1

### NATIVE STRUCTURE PLANTING TREE/SHRUB MIX @ 2 metre centres

Code	Species	Plant Condition	Age + Transplant	Height cm	Quantity
AC	Acer campestre (15%)	Bagged	1+2	60-80	25
CA	Corylus avellana (15%)	Bagged	1+2	60-80	25
CM	Crataegus monogyna (30%)	Bagged	1+2	60-80	45
CS	Cornus sanguinea (10%)	Bagged	1+2	60-80	15
LV	Ligustrum vulgare (10%)	Bagged	1+2	60-80	15
FS	Fraxinus ssp (5%)	Bagged	1+2	60-80	10
IA	Ilex aquifolium (5%)	5L	1+1	40-60	10
SC	Salix caprea (10%)	Bagged	1+2	60-80	15

### BULB PLANTING

Code	Species	Size	No. / m2	Quantity
FG	Narcissus 'February Gold'	14/16+topsize	20	150
MH	Narcissus 'Mount Hood'	14/16+topsize	20	150
PLO	Pseudonarcissus lobularis	14/16+topsize	20	80

### GRASS AND WILDFLOWER MIXES

Proposed Meadow / Grass Mixes	Description	Composition	Sowing Rate
AZ	Front gardens - Quality lawn	100% grasses	50g/m2

### ORNAMENTAL SHRUBS & HERBACEOUS PLANTING

Hedge species such as *Carpinus betulus* and *Taxus baccata* must be planted in a double staggered row, 30cm apart.

Low ornamental hedge planting such as *Lavandula* and *Rosmarinus* should also be planted in a double staggered row, 20cm apart.

Unless otherwise indicated, all shrubs where possible to be planted in groups of 5 or more, except:

*Persicaria* to be planted in groups of 15-25

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
ACM	Acanthus mollis	Grade A	5L	4	15
ANH	Anemone x hybrida 'Honoree Jobert'	Grade A	5L	5	35
ABG	Abelia x grandiflora	40-60	3L	3	15
AFM	Aster x filiflorus 'Monch'	25-30	2L	4	27
BA	Berberis Amstelveden	30-40	3L	5	15
BUX	Buxus sempervirens 'Suffruticosa'	20-30	2L	5 LM	345
COE	Carex oshimensis 'Evergold'	30-40	3L	9	20
CPB	Carpinus betulus (hedge)	60-80	5L	3 LM	450
CAP	Choisya x dewitiana 'Aztec Pearl'	40-60	10L	3	15
CTR	Ceanothus thyrsiflorus var. 'Repens'	60-80	10L	4	6
CRZ	Crocosmia 'Zambesi'	60-80	10L	3	41
DCG	Deschampsia cespitosa 'Goldtau'	Grade A	10L	6	15
DEC	Delphinium elatum 'Cinderella'	Grade A	10L	6	10
DFX	Dryopteris filix-mas	30-40	10L	6	10
EAB	Escallonia 'Apple Blossom'	60-80	10L	3	10
EE	Elaeagnus x ebbingei	60-80	3L	3	8
EAG	Euonymus Emerald 'n' Gold	30-40	3L	4 LM	60
EPF	Echinacea purpurea 'Magnus'	Grade A	5L	8	20
GJB	Geranium 'Johnsons Blue'	Grade A	5L	6	50
GL	Grosselia littoralis	60-80	3L	3	10
HIR	Hebe rakianensis	20-30	3L	6	25
HSA	Hebe 'Sapphire'	40-60	3L	3	13
HYP	Hypericum x messerianum	30-40	3L	4	50
LAV	Lavandula 'Hidcote'	20-30	3L	5 LM	395
OH	Oleandra haasti	40-60	10L	3 LM	70
OB	Oxanthalia burkeoides	40-60	10L	2	7
PAS	Persicaria amplexicaulis 'Firtale'	Grade A	2L	6	80
PHV	Philadelphus 'Virginal'	60-80	10L	3	10
PHF	Phlox frutescens	40-60	10L	4	45
PJV	Potentilla fruticosa 'Jackman's Variety'	40-60	10L	3 LM	25
RAK	Rosa 'Kent'	30-40	3L	5	10
RH	Rosa 'Herfordshire'	30-40	3L	5	10
RO	Rosmarinus officinalis 'Miss Jessopp's Upright'	40-60	3L	3 LM	25
RUD	Rudbeckia fulgida var. 'deamii'	Grade A	5L	7	10
SLW	Salvia 'Love and Wishes'	30-40	3L	5	35
SNG	Salvia nemerosa 'Caradonna'	30-40	3L	5	25
SS	Senecio Sunshine	40-60	10L	3	10
SG	Spiraea Goldflame	30-40	10L	3	25
SKM	Skimmia 'Kew Green'	40-60	12L	3	15
SBZ	Stachys byzantina	30-40	3L	5	15
SLV	Stipa gigantea	30-40	3L	3	12
TB	Taxus baccata (hedging)	40-60	10L	3 LM	67
VD	Viburnum davidii	40-60	10L	3	12
VTEP	Viburnum tinus 'Eve Price'	40-60	10L	3	10
WBR	Weigela 'Bristol Ruby'	40-60	10L	3	10

### SHRUB MIXES

PAS/GJB/MV/RTR all to be planted at front of planting area  
ACM to be planted at the back of the planting area.  
All plants to be planted in groups of 5-9, except ACM, KRS and EIC which are planted individually.

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
COE (15%)	Carex oshimensis 'Evergold'	30-40	3L	9	40
EPWS (5%)	Echinacea purpurea 'White Swan'	Grade A	5L	8	15
EPWS (5%)	Echinacea purpurea 'Magnus'	Grade A	5L	8	15
GJB (15%)	Geranium 'Johnsons Blue'	Grade A	5L	6	25
KRS (10%)	Kniphofia 'Royal Standard'	Grade A	3L	7	20
SCV (20%)	Salvia chamaecypariss	20-30	3L	8	45
SNG (20%)	Salvia nemerosa 'Caradonna'	30-40	3L	5	30
PAS (10%)	Persicaria affinis 'Superba'	Grade A	2L	9	25

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
ANH (15%)	Anemone x hybrida 'Honoree Jobert'	Grade A	5L	5	25
CRZ (5%)	Crocosmia 'Zambesi'	60-80	10L	3	5
DCG (10%)	Deschampsia cespitosa 'Goldtau'	Grade A	10L	6	20
DEC (10%)	Delphinium elatum 'Cinderella'	Grade A	10L	6	20
DMS (10%)	Delphinium 'Morning Sunrise'	Grade A	10L	6	20
EBU (5%)	Erythronium 'Bowie Mauve'	30-40	3L	7	10
PHF (5%)	Phlox frutescens	40-60	10L	4	6
SG (20%)	Spiraea Goldflame	30-40	10L	3	20
STG (10%)	Stipa gigantea	30-40	3L	3	10

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
ACM (10%)	Acanthus mollis	Grade A	5L	4	20
CAP (25%)	Choisya x dewitiana 'Aztec Pearl'	40-60	10L	3	40
RO (20%)	Rosmarinus officinalis 'Miss Jessopp's Upright'	40-60	3L	3	30
SKW (20%)	Skimmia 'Kew Green'	40-60	10L	3	30
SS (25%)	Senecio Sunshine	40-60	10L	3	40

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
ACM (15%)	Acanthus mollis	Grade A	5L	4	20
AFCG (25%)	Achillea filipendulina 'Cloth of Gold'	Grade A	3L	4	30
CAP (10%)	Choisya x dewitiana 'Aztec Pearl'	40-60	10L	3	10
EE (10%)	Elaeagnus x ebbingei	60-80	3L	2	7
EPFC (20%)	Eupatorium cannabinum	60-80	3L	4	25
EAB (10%)	Escallonia 'Apple Blossom'	60-80	10L	3	10
WBR (10%)	Weigela 'Bristol Ruby'	40-60	10L	3	10

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
COE (15%)	Carex oshimensis 'Evergold'	30-40	3L	9	30
EPWS (5%)	Echinacea purpurea 'Magnus'	Grade A	5L	8	10
GMW (15%)	Geranium macrorhizum 'White Ness'	Grade A	5L	6	20
KRS (10%)	Kniphofia 'Royal Standard'	Grade A	3L	7	15
HEL (20%)	Helleborus x hybridus	Grade A	3L	7	25
SLW (20%)	Salvia 'Love and Wishes'	30-40	3L	5	20
PAS (10%)	Persicaria affinis 'Superba'	Grade A	2L	9	20
RUD (5%)	Rudbeckia fulgida var. 'deamii'	Grade A	5L	7	10

### SHRUB MIX 6

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
CAP (5%)	Choisya x dewitiana 'Aztec Pearl'	40-60	10L	3	5
DCG (10%)	Deschampsia cespitosa 'Goldtau'	Grade A	10L	6	15
GMW (15%)	Geranium macrorhizum 'White Ness'	Grade A	5L	6	20
KRS (10%)	Kniphofia 'Royal Standard'	Grade A	3L	7	16
HAS (20%)	Hebe 'Sapphire'	40-60	3L	3	15
PHF (5%)	Phlox frutescens	40-60	10L	4	5
SG (20%)	Spiraea Goldflame	30-40	10L	3	15
SS (5%)	Senecio Sunshine	40-60	10L	3	5
STG (10%)	Stipa gigantea	30-40	3L	3	7

### GROUNDCOVER CLIMBERS AND WALL PLANTS

Code	Species	Height/ spread cm	Pot size (Litres)	No. / m2	Quantity
CLA	Clematis alpina	40-60	SPOT	2	2
FCG	Fremontodendron 'California Glory'	40-60	5L	SPOT	7
HGR	Hedera 'Green Ripple'	30-40	3L	3 LM	210
HMM	Hydrangea macrophylla 'Mariesii Perfecta'	100-120	20-30L	SPOT	2
HYPF	Hydrangea anomala subsp. 'petalis'	100-120	20-30L	SPOT	6
PFV	Pyracantha rogersiana 'flava'	40-60	5L	SPOT	8
PVIV	Parthenocissus tricuspidata 'Veitchi'	40-60	5L	SPOT	17
RAS	Rosa 'A Shropshire Lad'	40-60	5L	SPOT	8
RWS	Rosa 'Westerland'	40-60	5L	SPOT	8
WFM	Wisteria floribunda 'MultiJuga'	40-60	5L	SPOT	8

### FEATURE SHRUBS

Code	Species	Form	Girth cm	Height cm	Plant condition	Quantity
ABL	Amelanchier 'Baierina'	Half standard	6-8cm	200	15L	1
BUX (balls)	Buxus sempervirens	Bushy	-	> 60cm	15L	12
CAB	Ceanothus 'Concha'	Bushy	-	100-120	15L	2
CKS	Cornus kousa 'Steeple'	Half standard	6-8cm	200	15L	1
MC	Mahonia x Media 'Gross'	-	-	100-120	20-30L	2
MISC	Mahonia 'Soft Caress'	Bushy	-	60-80	20L	2
PCA	Philadelphus coronatus 'Aureus'	Half standard	-	100-120	20-30L	3
PHM	Philadelphus 'Manteau de Hermine'	Bushy	-	60-80	10L	2
PRR	Photinia x fraseri 'Red Robin'	-	-	100-120	20-30L	2
SVS	Spring vulgaris 'Sensation'	-	-	100-120	20-30L	2
VPM	Viburnum plicatum 'Marquet'	Bushy	-	100-120	20-30L	1

**NOTE:** These implementation and maintenance guidelines are for planning purposes only to indicate the level of workmanship to be specified and do not constitute a detailed specification.

1. **GENERAL**
  - 1.1 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.2 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.3 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.4 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.5 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.6 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.7 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.8 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.9 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.10 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.11 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.12 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.13 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.14 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.15 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.16 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.17 All trees up to and including selected standards are to be supported with single 75mm diameter stakes.
  - 1.18 All trees up to