



Our Ref;1-046/TN/001
18 December 2020

David Uncle
Hertfordshire County Council
Country Hall
Pegs Lane
Hertford
SG13 8DN

BY EMAIL ONLY

Dear David,

RE: NORTHAW HOUSE, HATFIELD – ATTENUATION POND HALF DRAIN DOWN TIME

SCOPE

This technical note has been prepared to calculate the half drain down time of the attenuation basin provided as part of the proposed drainage design for Northaw House, Hatfield (drainage layout as shown on 1-046-CCE-XX-XX-DR-C-001, 002 & 003).

- Maximum attenuation pond required during critical storm event (the 100yr+40%cc, 960 minute winter event as of network model calculations) = 799m³
- Maximum discharge rate of attenuation pond (QBAR runoff rate) = 4.50 l/s (or 0.0045m³ / s)

Therefore;

$$\frac{799m^3}{2} = 399.50m^3$$
$$\frac{399.50m^3}{0.0045} = 88,778 \text{ seconds (24.66 hours)}$$

Allowing for potential of 10% inefficiency of hydro-brake flow control due to low head;

$$88,778 \text{ seconds (24.66 hours)} \times 1.10 = 97,656 \text{ seconds (27.13 hours)}$$



+44 (0)1223 668 574 | enquires@civilistix.com | www.civilistix.com
Registration No. 11883036 | VAT No. 318936670

Specialists in Highway, Drainage & Utility Infrastructure

If you have any queries regarding the above, please do not hesitate to contact us.

Yours Sincerely,



Dan Martin, BSc, CEng MICE



for **CIVILISTIX CONSULTING ENGINEERS LIMITED**