

Wendy Birks

From: BCTAdmin@thameswater.co.uk
Sent: 19 March 2018 10:03
To: Planning
Subject: 3rd Party Planning Application - 6/2018/0171/MAJ

WARNING: This email originated outside the WHBC Network. Please be extra vigilant when opening attachments or clicking links.

Head Of Development Control
Welwyn Hatfield District Council
Council Offices, Campus East
Welwyn Garden City
Hertfordshire
AL8 6AE

Our DTS Ref: 26322
Your Ref: 6/2018/0171/MAJ

19 March 2018

Dear Sir/Madam

Re: FORMER SHREDDED WHEAT FACTORY, BRIDGE ROAD, WELWYN GARDEN CITY, HERTFORDSHIRE, AL8 6UN

Waste Comments

Thames Water requests that the Applicant should incorporate within their proposal, protection to the property by installing for example, a non-return valve or other suitable device to avoid the risk of backflow at a later date, on the assumption that the sewerage network may surcharge to ground level during storm conditions.

Thames Water recommends the installation of a properly maintained fat trap on all catering establishments. We further recommend, in line with best practice for the disposal of Fats, Oils and Grease, the collection of waste oil by a contractor, particularly to recycle for the production of bio diesel. Failure to implement these recommendations may result in this and other properties suffering blocked drains, sewage flooding and pollution to local watercourses.

A Trade Effluent Consent will be required for any Effluent discharge other than a 'Domestic Discharge'. Any discharge without this consent is illegal and may result in prosecution. (Domestic usage for example includes - toilets, showers, washbasins, baths, private swimming pools and canteens). Typical Trade Effluent processes include: - Laundrette/Laundry, PCB manufacture, commercial swimming pools, photographic/printing, food preparation, abattoir, farm wastes, vehicle washing, metal plating/finishing, cattle market wash down, chemical manufacture, treated cooling water and any other process which produces contaminated water. Pre-treatment, separate metering, sampling access etc, may be required before the Company can give its consent. Applications should be made at <https://wholesale.thameswater.co.uk/Wholesale-services/Business-customers/Trade-effluent> or alternatively to Waste Water Quality, Crossness STW, Belvedere Road, Abbeywood, London. SE2 9AQ. Telephone: 020 3577 9200.

No piling shall take place until a piling method statement (detailing the depth and type of piling to be undertaken and the methodology by which such piling will be carried out, including measures to prevent and minimise the potential for damage to subsurface sewerage infrastructure, and the programme for the works) has been submitted to and approved in writing by the local planning authority in consultation with Thames Water. Any piling must be undertaken in accordance with the terms of the approved piling method statement. Reason: The proposed works will be in close proximity to underground sewerage utility infrastructure. Piling has the potential to impact on local

underground sewerage utility infrastructure. The applicant is advised to contact Thames Water Developer Services on 0800 009 3921 to discuss the details of the piling method statement.

'We would expect the developer to demonstrate what measures he will undertake to minimise groundwater discharges into the public sewer. Groundwater discharges typically result from construction site dewatering, deep excavations, basement infiltration, borehole installation, testing and site remediation. Any discharge made without a permit is deemed illegal and may result in prosecution under the provisions of the Water Industry Act 1991. Should the Local Planning Authority be minded to approve the planning application, Thames Water would like the following informative attached to the planning permission: "A Groundwater Risk Management Permit from Thames Water will be required for discharging groundwater into a public sewer. Any discharge made without a permit is deemed illegal and may result in prosecution under the provisions of the Water Industry Act 1991. We would expect the developer to demonstrate what measures he will undertake to minimise groundwater discharges into the public sewer. Permit enquiries should be directed to Thames Water's Risk Management Team by telephoning 02035779483 or by emailing wwqriskmanagement@thameswater.co.uk. Application forms should be completed on line via www.thameswater.co.uk/wastewaterquality."

With the information provided Thames Water, has been unable to determine the waste water infrastructure needs of this application. Should the Local Planning Authority look to approve the application ahead of further information being provided, we request that the following 'Grampian Style' condition be applied - "Development shall not commence until a drainage strategy detailing any on and/or off site drainage works, has been submitted to and approved by, the local planning authority in consultation with the sewerage undertaker. No discharge of foul or surface water from the site shall be accepted into the public system until the drainage works referred to in the strategy have been completed". Reason - The development may lead to sewage flooding; to ensure that sufficient capacity is made available to cope with the new development; and in order to avoid adverse environmental impact upon the community. Should the Local Planning Authority consider the above recommendation is inappropriate or are unable to include it in the decision notice, it is important that the Local Planning Authority liaises with Thames Water Development Control Department (telephone 0203 577 9998) prior to the Planning Application approval.

Water Comments

With regard to water supply, this comes within the area covered by the Affinity Water Company. For your information the address to write to is - Affinity Water Company The Hub, Tamblin Way, Hatfield, Herts, AL10 9EZ - Tel - 0845 782 3333.

Supplementary Comments

We require the foul water drainage strategy to be enhanced by agreeing the point of connections to the public sewer system in Bridge Road and peak flow rates at each point. We also need confirmation that the public sewer system is able to accommodate the proposed 20 l/s of peak discharge due to the proposed four pumping stations. We require the surface water drainage strategy to be enhanced by determining the existing points of connection to the public sewer and estimated peak discharge rates for the pre-development flows. We then need this compared with the supplied proposed discharge rates to clearly indicate a net reduction in peak discharge due to this redevelopment.

Yours faithfully
Development Planning Department

Development Planning,
Thames Water,
Maple Lodge STW,
Denham Way,
Rickmansworth,
WD3 9SQ
Tel:020 3577 9998

Email: devcon.team@thameswater.co.uk

This is an automated email, please do not reply to the sender. If you wish to reply to this email, send to devcon.team@thameswater.co.uk