

## Michael Robinson

---

**From:** Michael Robinson  
**Sent:** 19 April 2021 10:47  
**To:** Michael Robinson  
**Subject:** FW: Application 6/2021/0451/PN14

**From:** Terry Vincent  
**Sent:** 15 March 2021 15:06  
**To:** Michael Robinson <[m.robinson@welhat.gov.uk](mailto:m.robinson@welhat.gov.uk)>  
**Subject:** RE: Application 6/2021/0451/PN14

Hi Michael,

That looks fine to me. I have will include our requirements in terms of working hours and best practice that will need to be followed.

Thanks.

1. All works and ancillary operations which are audible at the site boundary, or at such other place as may be agreed with the Council, shall be carried out only between the hours of :  
8.00am and 6.00pm on Mondays to Fridays  
8.00am and 1.00pm Saturdays  
and at no time on Sundays and Bank Holidays
2. The best practicable means, as defined in section 72 of the Control of Pollution Act 1974, to reduce noise to a minimum shall be employed at all times
3. All plant and machinery in use shall be properly silenced and maintained in accordance with the manufacturers' instructions
4. All compressors shall be sound reduced models, fitted with properly lined and sealed acoustic covers, which shall be kept closed whenever the machines are in use. All ancillary pneumatic percussive tools shall be fitted with mufflers or silencers of the type recommended by the manufactures.
5. All machines in intermittent use shall be shut down during intervening periods between work, or throttled down to a minimum. Noise emitting equipment, which is required to operate continuously, shall be housed in suitable acoustic enclosures.
6. Items of plant and equipment shall be maintained in good condition so that extraneous noise from mechanical vibration, squeaking or creaking is reduced to a minimum.
7. All pile driving shall be carried out by a recognised noise reducing system.
8. Where practical, rotary drills and bursters, actuated by hydraulic or electric power shall be used for excavating hard material
9. In general, equipment for breaking concrete and the like, shall be hydraulically actuated.
10. 'BS 5228 Noise Control on Construction Sites' should be referred to for guidance in respect of all work carried out by the developer, their main contractor and any sub contractors.

11. Any emergency deviation from these conditions shall be notified to the Council without delay
12. Any planned deviations from these conditions for special technical reasons, shall be negotiated with Council at least 14 days prior to the commencement of the specific work.
13. Permissible noise levels are not specified at this stage.

### **Dust control**

1. All efforts shall be made to reduce dust generation to a minimum
2. Stock piles of materials for use on the site or disposal, that are likely to generate dust, shall be sited so as to minimise any nuisance to residents or neighbouring businesses. Materials for disposal shall be moved off site as quickly as possible.
3. Water sprays shall be used, as and when necessary, to reduce dust from particularly "dusty" activities or stock piles.

### **Kind Regards**

**Terry Vincent PGDip Acoustics AMIOA**  
**Environmental Health Technical Officer**  
**Welwyn Hatfield Borough Council**  
**Telephone: 01707 357 934**  
[t.vincent@welhat.gov.uk](mailto:t.vincent@welhat.gov.uk)

*Working better, together*

[www.welhat.gov.uk](http://www.welhat.gov.uk)  
[@WelHatCouncil](#)  
[Welwyn Hatfield Borough Council](#)

---

**From:** [Alison.Laing@hightownha.org.uk](mailto:Alison.Laing@hightownha.org.uk) [mailto:[Alison.Laing@hightownha.org.uk](mailto:Alison.Laing@hightownha.org.uk)]  
**Sent:** 10 March 2021 17:07  
**To:** Michael Robinson <[m.robinson@welhat.gov.uk](mailto:m.robinson@welhat.gov.uk)>  
**Subject:** RE: Application 6/2021/0451/PN14

**\*\* WARNING: This email originated outside the WHBC Network. Please be extra vigilant when opening attachments or clicking links \*\***

Hello Michael


We have consulted with our potential demolition contractors and they have advised as follows:-

Initially a soft strip of the building would be carried out to remove any furnishings, floorings, door frames etc and then the building would be demolished using a 360degree excavator with either a rotating pulveriser or rotating excavator grapple to take the building down in stages.

Please let me know if you need any further information.

**Alison Laing**

Head of Projects, Development Department  
DDI: 01442 292369 [alison.laing@hightownha.org.uk](mailto:alison.laing@hightownha.org.uk)  
Mob : 07584 342586



**Hightown**

Hightown Housing Association Ltd Hightown House Maylands Avenue Hemel Hempstead HP2 4XH  
T 01442 292300 Web: [www.hightownha.org.uk](http://www.hightownha.org.uk)

A Charitable Housing Association

